



Automation1 XL5e High-Performance Linear Digital Drive

HARDWARE MANUAL

Revision 1.02



GLOBAL TECHNICAL SUPPORT

Go to the [Global Technical Support Portal](#) for information and support about your Aerotech, Inc. products. The website supplies software, product manuals, Help files, training schedules, and PC-to-PC remote technical support. If necessary, you can complete Product Return (RMA) forms and get information about repairs and spare or replacement parts. To get help immediately, contact a service office or your sales representative. Include your customer order number in your email or have it available before you call.

This manual contains proprietary information and may not be reproduced, disclosed, or used in whole or in part without the express written permission of Aerotech, Inc. Product names mentioned herein are used for identification purposes only and may be trademarks of their respective companies.

Copyright © 2019-2021, Aerotech, Inc., All rights reserved.



Table of Contents

Automation1 XL5e High-Performance Linear Digital Drive	1
Table of Contents	3
List of Figures	5
List of Tables	7
EU Declaration of Conformity	9
Safety Procedures and Warnings	11
Installation Overview	13
Chapter 1: Introduction	15
1.1. Electrical Specifications	19
1.2. Mechanical Specifications	20
1.2.1. Mounting and Cooling	20
1.2.2. Dimensions	21
1.3. Environmental Specifications	23
1.4. Drive and Software Compatibility	24
Chapter 2: Installation and Configuration	25
2.1. Input Power Connections	26
2.1.1. Control Supply Connector	26
2.1.2. Motor Supply Connector	27
2.2. Motor Power Output Connector	28
2.2.1. Brushless Motor Connections	29
2.2.1.1. Brushless Motor Powered Motor and Feedback Phasing	30
2.2.1.2. Brushless Motor Unpowered Motor and Feedback Phasing	31
2.2.2. DC Brush Motor Connections	32
2.2.2.1. DC Brush Motor Phasing	33
2.2.3. Stepper Motor Connections	34
2.2.3.1. Stepper Motor Phasing	35
2.3. Feedback Connector	36
2.3.1. Primary Encoder Inputs	37
2.3.1.1. Square Wave Encoder	38
2.3.1.2. Absolute Encoder	39
2.3.1.3. Sine Wave Encoder [-MX2/-MX3 Option]	40
2.3.1.4. Encoder Phasing	42
2.3.2. Hall-Effect Inputs	43
2.3.3. Thermistor Input	44
2.3.4. Encoder Fault Input	45
2.3.5. End of Travel and Home Limit Inputs	46
2.3.5.1. End of Travel and Home Limit Phasing	48
2.3.6. Brake Outputs	49
2.4. Safe Torque Off Input (STO)	50
2.4.1. STO Standards	52
2.4.2. STO Functional Description	53
2.4.3. STO Startup Validation Testing	54
2.4.4. STO Diagnostics	55
2.5. Auxiliary I/O Connector	56
2.5.1. Auxiliary Encoder Inputs	57
2.5.1.1. Square Wave Encoder	58
2.5.1.2. Absolute Encoder	59
2.5.1.3. Sine Wave Encoder [-MX3 Option]	60
2.5.2. Position Synchronized Output (PSO)	62
2.5.3. Digital Outputs	64
2.5.4. Digital Inputs	67
2.5.5. High-Speed Inputs	69
2.5.6. Analog Output 0	70
2.5.7. Analog Input 0 (Differential)	71
2.6. Brake Power Supply Connector	72
2.7. HyperWire Interface	73
2.8. Sync Port	74

2.9. System Interconnection	75
2.10. PC Configuration and Operation Information	77
Chapter 3: -EB1 I/O Option Board	79
3.1. Digital Outputs [-EB1]	80
3.2. Digital Inputs [-EB1]	84
3.3. Analog Outputs [-EB1]	87
3.4. Analog Inputs [-EB1]	88
3.5. Position Synchronized Output Interface [-EB1]	89
Chapter 4: Cables and Accessories	91
4.1. Joystick Interface	92
4.2. Handwheel Interface	94
Chapter 5: Maintenance	95
5.1. Preventative Maintenance	96
5.2. Fuse Specifications	97
Appendix A: Warranty and Field Service	99
Appendix B: Voltage Selection Operation	101
Appendix C: Revision History	103
Index	105

List of Figures

Figure 1-1:	XL5e High Performance Linear Amplifier	15
Figure 1-2:	Functional Diagram	18
Figure 1-3:	Dimensions	21
Figure 1-4:	Dimensions [-EB1]	22
Figure 2-1:	Control Supply Connections	26
Figure 2-2:	Motor Supply Connections	27
Figure 2-3:	Brushless Motor Configuration	29
Figure 2-4:	Positive Motor Direction	30
Figure 2-5:	Encoder and Hall Signal Diagnostics	30
Figure 2-6:	Brushless Motor Phasing Oscilloscope Example	31
Figure 2-7:	Brushless Motor Phasing Goal	31
Figure 2-8:	DC Brush Motor Configuration	32
Figure 2-9:	DC Brush Motor Configuration	32
Figure 2-10:	Positive Motor Direction	33
Figure 2-11:	Stepper Motor Configuration	34
Figure 2-12:	Positive Motor Direction	35
Figure 2-13:	Square Wave Encoder Schematic (Feedback Connector)	38
Figure 2-14:	Absolute Encoder Schematic (Feedback Connector)	39
Figure 2-15:	Sine Wave Encoder Phasing Reference Diagram	40
Figure 2-16:	Sine Wave Encoder Schematic (Feedback Connector)	41
Figure 2-17:	Encoder Phasing Reference Diagram (Standard)	42
Figure 2-18:	Position Feedback in the Diagnostic Display	42
Figure 2-19:	Hall-Effect Inputs Schematic (Feedback Connector)	43
Figure 2-20:	Thermistor Input Schematic (Feedback Connector)	44
Figure 2-21:	Encoder Fault Input Schematic (Feedback Connector)	45
Figure 2-22:	End of Travel and Home Limit Input Connections	47
Figure 2-23:	End of Travel and Home Limit Input Schematic (Feedback Connector)	47
Figure 2-24:	End of Travel and Home Limit Input Diagnostic Display	48
Figure 2-25:	Brake Connected to the 25-Pin Feedback Connector (Typical)	49
Figure 2-26:	Typical Configuration	51
Figure 2-27:	STO Timing	55
Figure 2-28:	Square Wave Encoder Interface (Aux I/O Connector)	58
Figure 2-29:	Absolute Encoder Schematic (Auxiliary I/O Connector)	59
Figure 2-30:	Sine Wave Encoder Phasing Reference Diagram	60
Figure 2-31:	Sine Wave Encoder Schematic (Auxiliary I/O Connector)	61
Figure 2-32:	PSO Interface	63
Figure 2-33:	Digital Output Schematic (Aux I/O Connector)	65
Figure 2-34:	Digital Outputs Connected in Current Sourcing Mode	66
Figure 2-35:	Digital Outputs Connected in Current Sinking Mode	66
Figure 2-36:	Digital Inputs Schematic (Aux I/O Connector)	67
Figure 2-37:	Digital Inputs Connected to Current Sourcing Devices	68
Figure 2-38:	Digital Inputs Connected to Current Sinking Devices	68
Figure 2-39:	High-Speed Inputs	69
Figure 2-40:	Analog Output 0 Schematic	70
Figure 2-41:	Analog Input 0 Schematic	71
Figure 2-42:	System Wiring Drawing (Best Practice)	75
Figure 2-43:	System Interconnection Drawing (Best Practice)	76
Figure 3-1:	XL5e with -EB1 I/O Option Board Connectors	79

Figure 3-2:	Digital Outputs Schematic [-EB1]	82
Figure 3-3:	Digital Outputs Connected in Current Sourcing Mode [-EB1]	83
Figure 3-4:	Digital Outputs Connected in Current Sinking Mode [-EB1]	83
Figure 3-5:	Digital Inputs Schematic [-EB1]	85
Figure 3-6:	Digital Inputs Connected to Current Sourcing (PNP) Devices [-EB1]	86
Figure 3-7:	Digital Inputs Connected to Current Sinking (NPN) Devices [-EB1]	86
Figure 3-8:	Analog Output Typical Connection [-EB1]	87
Figure 3-9:	Analog Input Typical Connection [-EB1]	88
Figure 3-10:	PSO Output Sources Current	90
Figure 3-11:	PSO Output Sinks Current	90
Figure 3-12:	PSO TTL Outputs Schematic	90
Figure 4-1:	Two Axis Joystick Interface (to the Aux I/O of two drives)	92
Figure 4-2:	Two Axis Joystick Interface (to the I/O board)	93
Figure 4-3:	Handwheel Interconnection to Aux I/O Connector	94
Figure 4-4:	Handwheel Interconnection to the Aux I/O through a BBA32 Module	94
Figure B-1:	Voltage Selection Switch Access	102

List of Tables

Table 1-1: Feature Summary	16
Table 1-2: Linear Amplifier Specifications	19
Table 1-3: Mounting Specifications	20
Table 1-4: Environmental Specifications	23
Table 1-5: Drive and Software Compatibility	24
Table 2-1: Control Supply Wiring Specifications	26
Table 2-2: Mating Connector Part Numbers for the Control Supply Connector	26
Table 2-3: Motor Supply Connector Wiring Specifications	27
Table 2-4: Mating Connector Part Numbers for the Motor Supply Connector	27
Table 2-5: Motor Power Output Connector Pinout	28
Table 2-6: Mating Connector Part Numbers for the Motor Power Output Connector	28
Table 2-7: Wire Colors for Aerotech-Supplied Brushless Motor Cables	29
Table 2-8: Hall Signal Diagnostics	30
Table 2-9: DC Brush Voltage Output Configuration	32
Table 2-10: Wire Colors for Aerotech-Supplied DC Brush Motor Cables	32
Table 2-11: Wire Colors for Aerotech-Supplied Stepper Motor Cables	34
Table 2-12: Feedback Connector Pinout	36
Table 2-13: Mating Connector Part Numbers for the Feedback Connector	36
Table 2-14: Multiplier Options	37
Table 2-15: Primary Encoder Input Pins on the Feedback Connector	37
Table 2-16: Square Wave Encoder Specifications	38
Table 2-17: Sine Wave Encoder Specifications	40
Table 2-18: Hall-Effect Feedback Pins on the Feedback Connector	43
Table 2-19: Thermistor Input Pin on the Feedback Connector	44
Table 2-20: Encoder Fault Input Pin on the Feedback Connector	45
Table 2-21: End of Travel and Home Limit Pins on the Feedback Connector	46
Table 2-22: Brake Output Pins on the Feedback Connector	49
Table 2-23: Brake Control Specifications	49
Table 2-24: STO Connector Pinout	50
Table 2-25: Mating Connector Part Numbers for the STO Connector	50
Table 2-26: STO Electrical Specifications	51
Table 2-27: STO Standards	52
Table 2-28: STO Standards Data	52
Table 2-29: STO Signal Delay	54
Table 2-30: Motor Function Relative to STO Input State	54
Table 2-31: STO Timing	55
Table 2-32: Auxiliary I/O Connector Pinout	56
Table 2-33: Mating Connector Part Numbers for the Auxiliary I/O Connector	56
Table 2-34: Auxiliary Encoder Pins on the Auxiliary I/O Connector	57
Table 2-35: Square Wave Encoder Specifications	58
Table 2-36: Sine Wave Encoder Specifications	60
Table 2-37: PSO Specifications	62
Table 2-38: PSO Pins on the Auxiliary I/O Connector	62
Table 2-39: Digital Output Specifications	64
Table 2-40: Digital Output Pins on the Auxiliary I/O Connector	64
Table 2-41: Digital Input Specifications	67
Table 2-42: Digital Input Pins on the Auxiliary I/O Connector	67
Table 2-43: High-Speed Input Specifications	69

Table 2-44:	High-Speed Input Pins on the Auxiliary I/O Connector	69
Table 2-45:	Analog Output Specifications	70
Table 2-46:	Analog Output Pins on the Auxiliary I/O Connector	70
Table 2-47:	Analog Input Specifications	71
Table 2-48:	Analog Input Pins on the Auxiliary I/O Connector	71
Table 2-49:	Brake Power Supply Connector Pinout	72
Table 2-50:	Mating Connector Part Numbers for the Brake Power Supply Connector	72
Table 2-51:	HyperWire Card Part Number	73
Table 2-52:	HyperWire Cable Part Numbers	73
Table 2-53:	Sync-Related Functions	74
Table 2-54:	Sync Port Cables	74
Table 3-1:	Digital Output Specifications [-EB1]	80
Table 3-2:	Digital Output 1 Connector Pinout [-EB1]	81
Table 3-3:	Mating Connector Part Numbers for the Digital Output 1 Connector [-EB1]	81
Table 3-4:	Digital Output 2 Connector Pinout [-EB1]	81
Table 3-5:	Mating Connector Part Numbers for the Digital Output 2 Connector [-EB1]	81
Table 3-6:	Digital Input Specifications [-EB1]	84
Table 3-7:	Digital Input 1 Connector Pinout [-EB1]	84
Table 3-8:	Mating Connector Part Numbers for the Digital Input 1 Connector [-EB1]	84
Table 3-9:	Digital Input 2 Connector Pinout [-EB1]	85
Table 3-10:	Mating Connector Part Numbers for the Digital Input 2 Connector [-EB1]	85
Table 3-11:	Analog Output Specifications [-EB1]	87
Table 3-12:	Analog Output Connector Pinout [-EB1]	87
Table 3-13:	Mating Connector Part Numbers for the Analog Output Connector [-EB1]	87
Table 3-14:	Differential Analog Input Specifications [-EB1]	88
Table 3-15:	Analog Input Connector Pinout [-EB1]	88
Table 3-16:	Mating Connector Part Numbers for the Analog Input Connector [-EB1]	88
Table 3-17:	PSO Specifications [-EB1]	89
Table 3-18:	PSO Interface Connector Pinout [-EB1]	89
Table 3-19:	Mating Connector Part Numbers for the PSO Interface Connector [-EB1]	89
Table 4-1:	Standard Interconnection Cables	91
Table 5-1:	LED Description	95
Table 5-2:	Troubleshooting	95
Table 5-3:	Preventative Maintenance	96
Table 5-4:	Fuse Specifications	97

EU Declaration of Conformity

Manufacturer Aerotech, Inc.
Address 101 Zeta Drive
 Pittsburgh, PA 15238-2811
 USA
Product XL5e
Model/Types All

This is to certify that the aforementioned product is in accordance with the applicable requirements of the following directive(s):

2014/30/EU	Electromagnetic Compatibility (EMC)
2014/35/EU	Low Voltage Directive
2006/42/EC	Machinery Directive
2011/65/EU	RoHS 2 Directive
EU 2015/863	Amendment RoHS 3 Directive

and has been designed to be in conformity with the applicable requirements of the following standard(s) when installed and used in accordance with the manufacturer's supplied installation instructions.

EN 61010-1:2010/A1:2016	Safety Requirements for Electrical Equipment
EN 61800-3:2017	EMC Requirements for Power Drives
IEC 61800-5-1:2016	Electrical Safety for Power Drive Systems
IEC 61800-5-2:2016	Functional Safety for Power Drive Systems
EN 55011/55032:2015	Conducted and Radiated Emissions

**Authorized
Representative**

 / Simon Smith, European Director
 Aerotech Ltd
 The Old Brick Kiln, Ramsdell, Tadley
 Hampshire RG26 5PR
 UK

**Engineer Verifying
Compliance**

 / Alex Weibel
 Aerotech, Inc.
 101 Zeta Drive
 Pittsburgh, PA 15238-2811
 USA
 6/30/2021

Date



This page intentionally left blank.

Safety Procedures and Warnings



IMPORTANT: This manual tells you how to carefully and correctly use and operate the drive.

- Read all parts of this manual before you install or operate the drive or before you do maintenance to your system.
- To prevent injury to you and damage to the equipment, obey the precautions in this manual.
- All specifications and illustrations are for reference only and were complete and accurate as of the release of this manual. To find the newest information about this product, refer to www.aerotech.com.

If you do not understand the information in this manual, contact Aerotech Global Technical Support.



IMPORTANT: This product has been designed for light industrial manufacturing or laboratory environments. If the product is used in a manner not specified by the manufacturer:

- The protection provided by the equipment could be impaired.
- The life expectancy of the product could be decreased.



DANGER: To decrease the risk of electrical shock, injury, death, and damage to the equipment, obey the precautions that follow.

1. Before you do maintenance to the equipment, disconnect the electrical power.
2. Restrict access to the drive when it is connected to a power source.
3. Do not connect or disconnect electrical components, wires, and cables while this product is connected to a power source.
4. Wait at least ten (10) minutes after removing the power supply before doing maintenance or an inspection. Otherwise, there is the danger of electric shock.
5. Supply each operator with the necessary protection from live electrical circuits.
6. Make sure that all components are grounded correctly and that they obey the local electrical safety requirements.
7. Install the necessary precautions to supply safety and protection to the operator.



DANGER: System travel can cause crush, shear, or pinch injuries. Restrict access to all motor and stage parts while your system is connected to a power source.




WARNING: To prevent damage to the equipment and decrease the risk of electrical shock and injury, obey the precautions that follow.

1. Make sure that all system cables are correctly attached and positioned.
2. Do not use the cables or the connectors to lift or move this product.
3. Use this product only in environments and operating conditions that are approved in this manual.
4. Only trained operators should operate this equipment.

This page intentionally left blank.

Installation Overview

This image shows the order in which to make connections and settings that are typical to the XL5e. If a custom interconnect drawing was supplied with your system, that drawing is on your Storage Device and shows as a line item on your Sales Order in the Integration section.



1	Connect the motor to the amplifier Motor Output connector.	Section 2.2.
	Connect the motor to the amplifier Feedback connector.	Section 2.3.
2	Connect a PC or drive-based controller HyperWire port to the HyperWire In port.	Section 2.7.
3	Connect additional I/O as required by your application (if you purchased the I/O option).	Section 2.5./ Chapter 3
4	Connect the Safe Torque Off (STO).	Section 2.4.
5	Connect the power supply to the Control Supply connector.	Section 2.1.1.
6	Connect the motor power to the Motor Supply connector.	Section 2.1.2.

Figure 1: Installation Connection Overview

This page intentionally left blank.

Chapter 1: Introduction

The XL5e is a high-performance linear amplifier designed for motion control applications that require the highest positioning accuracy and lowest generated noise. The XL5e is factory configured for the specified AC input voltage, motor output voltage, and current. Refer to [Table 1-1](#) for a complete list of features and ordering options.




Figure 1-1: XL5e High Performance Linear Amplifier

Table 1-1: Feature Summary

Standard Features	
• 100 - 240 VAC control supply input	Section 2.1.1.
• Factory-configured motor supply AC input	Section 2.1.2.
• Line driver square wave quadrature encoder input for position and velocity feedback	Section 2.3.1.
• Absolute Encoder support on the Feedback Connector	Section 2.3.1.2.
• One fail-safe brake output	Section 2.3.6.
• Two STO sense inputs	Section 2.4.
• Line driver square wave auxiliary quadrature encoder input or output for PSO	Section 2.5.1.
• Absolute Encoder support on the Auxiliary I/O Connector	Section 2.5.1.2.
• Four digital user outputs	Section 2.5.3.
• Six digital user inputs	
▪ Four Digital Inputs	Section 2.5.4.
▪ Two High-Speed Inputs	Section 2.5.5.
• One 16-bit analog output (± 10 V)	Section 2.5.6.
• One 16-bit differential analog input (± 10 V)	Section 2.5.7.
Options	
Peak Current	
-10	10 A Peak
-20	20 A Peak
Bus Voltage	
-VB4	± 40 VDC Bus Voltage (available for -10 or -20 option boards)
-VB5	± 60 VDC Bus Voltage (available for -10 option board)
-VB6	± 80 VDC Bus Voltage (available for -10 option board)
Input Line Voltage	
-VL1	120 VAC
-VL2	240 VAC
-VL3	100 VAC
-VL4	200 VAC
Expansion Board	
-EB0	No expansion board
-EB1	I/O expansion board <ul style="list-style-type: none"> • Three 16-bit analog outputs (± 10 V) • Three 16-bit differential analog inputs (± 10 V) • 16 digital logic inputs (5 - 24 VDC), may be connected in current sourcing or sinking mode • 16 digital logic outputs (5 - 24 VDC), user defined as current sourcing or sinking • Digital logic laser firing (PSO) output

Options (Continued)	
Multiplier Section 2.3.1.3.	
-MX0	No encoder multiplier
-MX2	Interpolation circuit allowing for analog sine wave input on the primary encoder channel with an interpolation factor of 65,536
-MX3	Interpolation circuit allowing for analog sine wave input on the primary encoder channel with an interpolation factor of 65,536 and an auxiliary encoder channel with an interpolation factor of 16,384.
PSO Section 2.5.2.	
-PSO1	One-axis PSO firing (includes One-axis Part-Speed PSO)
-PSO2	Two-axis PSO firing (includes Two-axis Part-Speed PSO)
-PSO3	Three-axis PSO firing (includes Three-axis Part-Speed PSO)
-PSO5	Two-axis Part-Speed PSO firing, which uses the PSO firing circuit based off of the commanded vector velocity of up to 2 axes (includes One-Axis PSO).
-PSO6	Three-axis Part-Speed PSO firing, which uses the PSO firing circuit based off of the commanded vector velocity of 3 or more axes (includes One-Axis PSO).
Version	
-DEFAULT	Firmware Matches Software Line
-LEGACY	Legacy Firmware Version X.XX.XXX

The block diagram that follows shows a summary of the connector signals.




Figure 1-2: Functional Diagram

1.1. Electrical Specifications

Table 1-2: Linear Amplifier Specifications

	XL5e-10-VB4	XL5e-20-VB4	XL5e-10-VB5	XL5e-10-VB6
Nominal Motor Bus Voltage	±40 V	±40 V	±60 V	±80 V
Peak Output Current	10 A _{pk}	20 A _{pk}	10 A _{pk}	10 A _{pk}
Continuous Output Current @ 25°C ⁽¹⁾⁽²⁾	5 A _{pk} / 5 A _{pk}	5 A _{pk} / 9 A _{pk}	3.2 A _{pk} / 6 A _{pk}	2.5 A _{pk} / 4.5 A _{pk}
Continuous Output Current @ 35°C ⁽¹⁾⁽²⁾	4 A _{pk} / 5 A _{pk}	4 A _{pk} / 8 A _{pk}	2 A _{pk} / 5.5 A _{pk}	2 A _{pk} / 4 A _{pk}
Maximum Continuous Total Power Dissipation ⁽²⁾⁽³⁾⁽⁴⁾	340 W / 585 W			
Peak Amplifier Power Dissipation per phase ⁽⁵⁾	1200 W			
Effective Heatsink Thermal Resistance ⁽²⁾	.15°C/W / .085°C/W			
Maximum Transistor Temperature	75°C			
Time to reach maximum temperature at maximum continuous power	10 minutes			
Motor Supply	Input Frequency	50-60 Hz		
	Inrush current	68 A _{pk} @ 240 V		
	AC Line Voltage	AC Input (Switch Selectable): 100 VAC (90 - 112 VAC) 120 VAC (103 - 127 VAC) 200 VAC (180 - 224 VAC) 240 VAC (207 - 254 VAC)		
	Input current (maximum, continuous)	7 A _{rms} @ 120 V / 3.5 A _{rms} @ 240 V		
	Control Supply	Input Frequency	50-60 Hz	
Inrush current		68 A _{pk} @ 240 V		
Input current (maximum, continuous)		.25 A _{rms}		
Current Loop Bandwidth	2500 Hz (software selectable)			
Minimum load resistance	0 Ω			
Minimum load inductance	0 H			
Modes of operation	Brushless, Brush, Stepper			
Protection Features	Peak current limit, Over temperature, RMS current limit, Dynamic power limit (SOA)			
Encoder Supply	5 V @ 500 mA			
<p>(1) AC or DC motor type with a 0 Ω winding resistance assumed.</p> <p>(2) The first value is for a stationary AC or DC motor. The second value is for a moving AC motor.</p> <p>(3) De-rate at temperatures above 25°C ambient.</p> <p>(4) Amplifier power dissipation is calculated as $(V_{bus} - V_{out}) \cdot I_{out}$ for each phase. A 40B configuration that drives 1 A into 0 Ω results in 40 W of power dissipation in the amplifier.</p> <p>(5) The XL5e amplifier has peak power-limiting circuitry to protect itself from damage. The Power Limiting bit in the Drive Status word indicates if this has occurred.</p>				

1.2. Mechanical Specifications

1.2.1. Mounting and Cooling

Install the XL5e in an IP54 compliant enclosure to comply with safety standards. Make sure that there is sufficient clearance surrounding the drive for free airflow and for the cables and connections.

Table 1-3: Mounting Specifications

		XL5e
Customer-Supplied Enclosure		IP54 Compliant
Weight		~11.31 kg
Mounting Hardware		M4 [#8] screws (four locations, not included)
Mounting Orientation		Vertical (typical)
Dimensions		Refer to Section 1.2.2. Dimensions
Minimum Clearance	Airflow	~25 mm
	Connectors	~100 mm
Operating Temperature		Refer to Section 1.3. Environmental Specifications

1.2.2. Dimensions




Figure 1-3: Dimensions




Figure 1-4: Dimensions [-EB1]

1.3. Environmental Specifications

Table 1-4: Environmental Specifications

Ambient Temperature	Operating: 0° to 40°C (32° to 104° F)
	Storage: -30° to 85°C (-22° to 185° F)
Humidity Non-condensing	The maximum relative humidity is 80% for temperatures that are less than 31°C and decreases linearly to 50% relative humidity at 40°C.
Operating Altitude	0 m to 2,000 m (0 ft to 6,562 ft) above sea level. If you must operate this product above 2,000 m or below sea level, contact Aerotech, Inc.
Pollution	Pollution Degree 2 Typically only nonconductive pollution occurs.
Operation	Use only indoors

1.4. Drive and Software Compatibility

This table shows the available drives and which version of the software first supported each drive. In the **Last Software Version** column, drives that show a specific version number are not supported after that version.

Table 1-5: Drive and Software Compatibility

Drive Type	First Software Version	Last Software Version
Automation1 XL5e	1.2.0	Current

Chapter 2: Installation and Configuration

Unpacking the Chassis



IMPORTANT: All electronic equipment and instrumentation is wrapped in antistatic material and packaged with desiccant. Ensure that the antistatic material is not damaged during unpacking.

Inspect the container of the XL5e for any evidence of shipping damage. If any damage exists, notify the shipping carrier immediately.

Remove the packing list from the XL5e container. Make sure that all the items specified on the packing list are contained within the package.

The documentation for the XL5e is on the included installation device. The documents include manuals, interconnection drawings, and other documentation pertaining to the system. Save this information for future reference. Additional information about the system is provided on the Serial and Power labels that are placed on the XL5e chassis.

The system serial number label contains important information such as the:

- Customer order number (please provide this number when requesting product support)
- Drawing number
- System part number

2.1. Input Power Connections

The XL5e has two AC input power connectors. One connector is for control power and the other connector is for motor power. For a full list of electrical specifications, refer to [Section 1.1](#).

2.1.1. Control Supply Connector

The Control Supply input supplies power to the communications and logic circuitry of the XL5e. The **L** input is connected to an internal fuse. Refer to [Table 5-4](#) for the internal fuse value and part number. The **N** input is not connected to an internal fuse. An external fuse will be required if **N** is not connected to Neutral.

The Control Supply contains an internal filter but you could be required to add an external filter for CE compliance. Install the external filter module as close as possible to the drive. Use a Schaffner FN2080 filter, an Aerotech UFM-ST noise filter module, or equivalent device.



IMPORTANT: Refer to local electrical safety requirements to correctly size external system wires.




Figure 2-1: Control Supply Connections

Table 2-1: Control Supply Wiring Specifications

Pin	Description	Recommended Wire Size
L	Line (L): 100-240 VAC Control Power Input	0.8 mm ² (#18 AWG)
N	Neutral (N) or 100-240 VAC Control Power Input with external fuse	0.8 mm ² (#18 AWG)
	Protective Ground	0.8 mm ² (#18 AWG)

Table 2-2: Mating Connector Part Numbers for the Control Supply Connector

Type	Aerotech P/N	Third Party P/N	Screw Torque: N·m	Wire Size: mm ² [AWG]
3-Pin Terminal Block	ECK00213	Phoenix 1754465	0.5 - 0.6	3.3 - 0.516 [12-30]

2.1.2. Motor Supply Connector

Motor power is applied to the **AC1** and **AC2** terminals of the XL5e Motor Supply connector. The **AC1** input is internally fused but the **AC2** input is not. An external fuse is required if **AC2** is not connected to Neutral. Refer to [Table 5-4](#) for the internal fuse part numbers.

Refer to Appendix B for information on how to change the factory-configured motor input voltage.



WARNING: Do not connect a voltage that exceeds the configured voltage. This will cause an internal fuse to open and could cause damage to components that are configured for ±60 VDC or ±80 VDC motor voltage options.



IMPORTANT: Refer to local electrical safety requirements to correctly size external system wires.



IMPORTANT: Make sure that the ground connection is installed correctly before you operate the XL5e.




Figure 2-2: Motor Supply Connections

Table 2-3: Motor Supply Connector Wiring Specifications

Pin	Description	Recommended Wire Size
AC1	Factory-Configure Motor Power Input	1.3 mm ² (#16 AWG)
AC2	Motor Power Input Common	1.3 mm ² (#16 AWG)
	Protective Ground	1.3 mm ² (#16 AWG)

Table 2-4: Mating Connector Part Numbers for the Motor Supply Connector

Type	Aerotech P/N	Third Party P/N	Screw Torque: N·m	Wire Size: mm ² [AWG]
3-Pin Terminal Block	ECK00213	Phoenix 1754465	0.5 - 0.6	3.3 - 0.516 [12-30]

2.2. Motor Power Output Connector



DANGER: Before you do maintenance to the equipment, disconnect the electrical power. Wait at least ten (10) minutes after removing the power supply before doing maintenance or an inspection. Otherwise, there is the danger of electric shock.

The XL5e can be used to drive the following motor types:

- Brushless (refer to [Section 2.2.1.](#))
- DC Brush (refer to [Section 2.2.2.](#))
- Stepper (refer to [Section 2.2.3.](#))

For a complete list of electrical specifications, refer to [Section 1.1.](#)



IMPORTANT: Refer to local electrical safety requirements to correctly size external system wires.

The 5-pin terminal block style motor output connector is located on the front panel. The pinout for this connector is shown in [Table 2-5.](#)

Table 2-5: Motor Power Output Connector Pinout

Pin	Description	Recommended Wire Size	Connector
	Earth Ground to Motor	1.3 mm ² (#16 AWG)	
RT	Brushless (No Connection) DC Brush - (Half Bus Voltage) Stepper Return	1.3 mm ² (#16 AWG)	
A	Brushless Phase A Motor Lead DC Brush + Stepper	1.3 mm ² (#16 AWG)	
B	Brushless Phase B Motor Lead DC Brush (No Connection) Stepper	1.3 mm ² (#16 AWG)	
C	Brushless Phase C Motor Lead DC Brush - (Full Bus Voltage) Stepper (No Connection)	1.3 mm ² (#16 AWG)	

Table 2-6: Mating Connector Part Numbers for the Motor Power Output Connector

Description	Aerotech P/N	Phoenix P/N	Tightening Torque (Nm)	Wire Size: AWG [mm ²]
5-Pin Terminal Block	ECK02393	1827622	0.22 - 0.25	2.5 - 0.05 [14-30]

2.2.1. Brushless Motor Connections

The configuration shown in Figure 2-3 is an example of a typical brushless motor connection.




Figure 2-3: Brushless Motor Configuration

Table 2-7: Wire Colors for Aerotech-Supplied Brushless Motor Cables

Pin	Wire Color Set 1 ⁽¹⁾	Wire Color Set 2	Wire Color Set 3	Wire Color Set 4
⊕	Green/Yellow & Shield ⁽²⁾	Green/Yellow & Shield	Green/Yellow & Shield	Green/Yellow & Shield
A	Black	Blue & Yellow	Black #1	Black & Brown
B	Red	Red & Orange	Black #2	Red & Orange
C	White	White & Brown	Black #3	Violet & Blue

(1) Wire Color Set #1 is the wire set typically used by Aerotech.
 (2) "&" indicates two wires (Red & Orange); "/" indicates a single wire (Green/White).

Brushless motors are commutated electronically by the controller. The use of Hall effect devices for commutation is recommended.

The controller requires that the Back-EMF of each motor phase be aligned with the corresponding Hall-effect signal. To ensure proper alignment, motor, Hall, and encoder connections should be verified using one of the following methods: *powered*, through the use of a test program; or *unpowered* using an oscilloscope. Both methods will identify the A, B, and C Hall/motor lead sets and indicate the correct connections to the controller. Refer to Section 2.2.1.1. for powered motor phasing or Section 2.2.1.2. for unpowered motor and feedback phasing.

For Aerotech-supplied systems, the motor, encoder and Hall sensors are correctly configured and connection adjustments are not necessary.

2.2.1.1. Brushless Motor Powered Motor and Feedback Phasing

Observe the state of the encoder and Hall-effect device signals in the Diagnostics section of the Status Utility.

Table 2-8: Hall Signal Diagnostics

Hall-Signal Status	Definition
--	0 V or logic low
ON	5 V or logic high




Figure 2-4: Positive Motor Direction




Figure 2-5: Encoder and Hall Signal Diagnostics

2.2.1.2. Brushless Motor Unpowered Motor and Feedback Phasing

Disconnect the motor from the controller and connect the motor in the test configuration shown in Figure 2-6. This method will require a two-channel oscilloscope, a 5V power supply, and six resistors (10,000 ohm, 1/4 watt). All measurements should be made with the probe common of each channel of the oscilloscope connected to a neutral reference test point (TP4, shown in Figure 2-6). Wave forms are shown while moving the motor in the positive direction.




Figure 2-6: Brushless Motor Phasing Oscilloscope Example

With the designations of the motor and Hall leads of a third party motor determined, the motor can now be connected to an Aerotech system. Connect motor lead A to motor connector A, motor lead B to motor connector B, and motor lead C to motor connector C. Hall leads should also be connected to their respective feedback connector pins (Hall A lead to the Hall A feedback pin, Hall B to Hall B, and Hall C to Hall C). The motor is correctly phased when the Hall states align with the Back EMF as shown in (Figure 2-7). Use the CommutationOffset parameter to correct for Hall signal misalignment.




Figure 2-7: Brushless Motor Phasing Goal

2.2.2. DC Brush Motor Connections

The configuration shown in Figure 2-8 is an example of a typical DC brush motor connection. Refer to Section 2.2.2.1. for information on motor phasing.

When you connect the motor between amplifier phases A and C, it will produce twice the nominal bus voltage across the motor. This is because phase C will generate the same voltage as phase A but with opposite polarity. To generate the nominal bus voltage, connect the motor between Phase A and RT. RT is the 0 V return path for the motor power supply.

Use the lowest voltage configuration possible to minimize heat generation in the amplifier.




Figure 2-8: DC Brush Motor Configuration




Figure 2-9: DC Brush Motor Configuration

Table 2-9: DC Brush Voltage Output Configuration

Connection	XL5e 20-VB4	XL5e10-VB4	XL5e10-VB5	XL5e10-VB6
A to C	80 V	80 V	120 V	160 V
A to RT	40 V	40 V	60 V	80 V

Table 2-10: Wire Colors for Aerotech-Supplied DC Brush Motor Cables

Pin	Wire Color Set 1 ⁽¹⁾	Wire Color Set 2	Wire Color Set 3
⊕	Green & White & Shield ⁽²⁾	Green/Yellow & Shield	Green/Yellow & Shield
A	Red & Orange	Red	Red & Orange
C	Yellow & Blue	Black	Yellow & Blue

(1) Wire Color Set #1 is the typical wire set used by Aerotech.
 (2) "&" (Red & Orange) indicates two wires; "/" (Green/White) indicates a single wire.

2.2.2.1. DC Brush Motor Phasing

A properly phased motor means that the positive motor lead should be connected to the $\emptyset A$ motor terminal and the negative motor lead should be connected to the $\emptyset C$ motor terminal. To determine if the motor is properly phased, connect a voltmeter to the motor leads of an un-powered motor:

1. Connect the positive lead of the voltmeter to the one of the motor terminals.
2. Connect the negative lead of the voltmeter to the other motor terminal.
3. Move or rotate the motor in the positive or clockwise (CW) direction by hand.




Figure 2-10: Positive Motor Direction

4. If the voltmeter indicates a negative value, swap the motor leads and move the motor by hand in the positive direction, again. When the voltmeter indicates a positive value, the motor leads have been identified.
5. Connect the motor lead from the positive lead of the voltmeter to the $\emptyset A$ motor terminal on the drive. Connect the motor lead from the negative lead of the voltmeter to the $\emptyset C$ motor terminal on the drive.

For Aerotech-supplied systems, the motor, encoder and Hall sensors are correctly configured and connection adjustments are not necessary.

2.2.3. Stepper Motor Connections

The configuration shown in Figure 2-11 is an example of a typical stepper motor connection. Refer to Section 2.2.3.1. for information on motor phasing.

In this case, the effective motor voltage is half of the applied bus voltage. For example, an 80V motor bus supply is needed to get 40V across the motor.




Figure 2-11: Stepper Motor Configuration

Table 2-11: Wire Colors for Aerotech-Supplied Stepper Motor Cables

Pin	Wire Color Set 1 ⁽¹⁾	Wire Color Set 2
⊕	Green/Yellow & Shield ⁽²⁾	Green/Yellow & Shield
A	Black	Brown
B	Red	Yellow
C	White	White & Red

(1) Wire Color Set #1 is the typical wire set used by Aerotech.
 (2) "&" (Red & Orange) indicates two wires; "/" (Green/White) indicates a single wire.

2.2.3.1. Stepper Motor Phasing

A stepper motor can be run with or without an encoder.

Without an Encoder: You do not need to phase the motor.

With an Encoder: Because the end of travel (EOT) limit inputs are relative to motor rotation, it is important to phase the motor.

Run a positive motion command. The motor is phased correctly if there is a positive scaling factor (determined by the CountsPerUnit parameters) and the motor moves in a clockwise direction when you view the motor from the front mounting flange (Figure 2-12). If the motor moves in a counterclockwise direction, swap the motor leads and re-run the command. After the motor has been phased, if you want to change the direction of positive motion, use the ReverseMotionDirection parameter.





Figure 2-12: Positive Motor Direction

For Aerotech-supplied systems, the motor, encoder and Hall sensors are correctly configured and connection adjustments are not necessary.

2.3. Feedback Connector

The connector pin assignment is shown in [Table 2-12](#) with detailed connection information in the following sections.

Table 2-12: Feedback Connector Pinout

Pin #	Description	In/Out/Bi	Connector
1	Reserved	N/A	
2	Motor Over Temperature Thermistor	Input	
3	+5V Power ⁽¹⁾	N/A	
4	Plug and Play Serial Data (for Aerotech stages only)	Bidirectional	
5	Hall-Effect Sensor B (brushless motors only)	Input	
6	Encoder Marker Reference Pulse -	Input	
	Absolute Encoder Clock -	Output	
7	Encoder Marker Reference Pulse +	Input	
	Absolute Encoder Clock +	Output	
8	Absolute Encoder Data -	Bidirectional	
9	Reserved	N/A	
10	Hall-Effect Sensor A (brushless motors only)	Input	
11	Hall-Effect Sensor C (brushless motors only)	Input	
12	Clockwise End of Travel Limit	Input	
13	Brake Output -	Output	
14	Encoder Cosine +	Input	
15	Encoder Cosine -	Input	
16	+5V Power ⁽¹⁾	N/A	
17	Encoder Sine +	Input	
18	Encoder Sine -	Input	
19	Absolute Encoder Data+	Bidirectional	
20	Signal Common	N/A	
21	Signal Common	N/A	
22	Home Switch Input	Input	
23	Encoder Fault Input	Input	
24	Counterclockwise End of Travel Limit	Input	
25	Brake Output +	Output	

(1) The maximum combined current output is 500 mA.

Table 2-13: Mating Connector Part Numbers for the Feedback Connector

Mating Connector	Aerotech P/N	Third Party P/N
25-Pin D-Connector	ECK00101	FCI DB25P064TXLF
Backshell	ECK00656	Amphenol 17E-1726-2

2.3.1. Primary Encoder Inputs

The primary encoder inputs are accessible through the Feedback connector. Use the PrimaryFeedbackType parameter to configure the XL5e to accept an encoder signal type.

Square Wave encoder signals: [Section 2.3.1.1.](#)

Absolute encoder signals: [Section 2.3.1.2.](#)

Sine Wave encoder signals (as permitted by the multiplier option): [Section 2.3.1.3.](#)

Refer to [Section 2.3.1.4.](#) for encoder feedback phasing.

Refer to [Section 2.5.](#) for the auxiliary encoder input on the Aux I/O connector.

Table 2-14: Multiplier Options

Option	Primary Encoder Accepts...	Auxiliary Encoder Accepts...
-MX0	Square Wave or Absolute encoders	Square Wave or Absolute encoders
-MX2	Sine Wave (high performance), Square Wave, or Absolute encoders	Square Wave or Absolute encoders
-MX3	Sine Wave (high performance), Square Wave, or Absolute encoders	Sine Wave (standard performance), Square Wave, or Absolute encoders



IMPORTANT: Physically isolate the encoder wiring from motor, AC power, and all other power wiring

Table 2-15: Primary Encoder Input Pins on the Feedback Connector

Pin #	Description	In/Out/Bi
3	+5V Power ⁽¹⁾	N/A
6	Encoder Marker Reference Pulse -	Input
	Absolute Encoder Clock -	Output
7	Encoder Marker Reference Pulse +	Input
	Absolute Encoder Clock +	Output
8	Absolute Encoder Data -	Bidirectional
14	Encoder Cosine +	Input
15	Encoder Cosine -	Input
16	+5V Power ⁽¹⁾	N/A
17	Encoder Sine +	Input
18	Encoder Sine -	Input
19	Absolute Encoder Data+	Bidirectional
20	Signal Common	N/A
21	Signal Common	N/A

(1) The maximum combined current output is 500 mA.

2.3.1.1. Square Wave Encoder

The drive accepts RS-422 square wave encoder signals. The drive will generate a feedback fault if it detects an invalid signal state caused by an open or shorted signal connection. Use twisted-pair wiring for the highest performance and noise immunity.

Table 2-16: Square Wave Encoder Specifications

Specification	Value
Encoder Frequency	10 MHz maximum (25 ns minimum edge separation)
x4 Quadrature Decoding	40 million counts/sec




Figure 2-13: Square Wave Encoder Schematic (Feedback Connector)

2.3.1.2. Absolute Encoder

The drive retrieves absolute position data along with encoder fault information through a serial data stream from the absolute encoder. Use twisted-pair wiring for the highest performance and noise immunity. You cannot echo an absolute encoder signal.

Refer to [Figure 2-14](#) for the serial data stream interface.

Refer to the Help file for information on how to set up your EnDat or BiSS absolute encoder parameters.




Figure 2-14: Absolute Encoder Schematic (Feedback Connector)

2.3.1.3. Sine Wave Encoder [-MX2/-MX3 Option]

The Sine Wave Encoder option provides higher positioning resolution by subdividing the fundamental output period of the encoder into smaller increments. The amount of subdivision is specified by the PrimaryEncoderMultiplicationFactor parameter. Use Encoder Tuning to adjust the value of the gain, offset, and phase balance controller parameters to get the best performance. For more information, refer to the Help file.

High resolution or high-speed encoders can require increased bandwidth for correct operation. Use the High Speed Mode of the PrimaryEncoderMultiplierSetup parameter to enable the high bandwidth mode. Because this mode increases sensitivity to system noise, use it only if necessary.

The XL5e can generate emulated encoder signals. These signals can be output on the Auxiliary Encoder (AUX) connector, SYNC port connector, or used internally by the PSO. Refer to the EncoderDivider and PrimaryEmulatedQuadratureDivider parameters and the encoder output functions in the Help file for more information.

For the highest performance, use twisted pair double-shielded cable with the inner shield connected to signal common and the outer shield connected to frame ground. Do not join the inner and outer shields in the cable.

Table 2-17: Sine Wave Encoder Specifications

Specification	Value	
	Primary	Auxiliary
Input Frequency (max)	450 kHz, 2 MHz	450 kHz
Input Amplitude ⁽¹⁾	0.6 to 1.75 Vpk-pk	
Interpolation Factor (max)	-MX2	65,536
	-MX3	65,536
-MX2/-MX3 Primary Encoder Channel Interpolation Latency	800 nsec (analog input to quadrature output)	
Input Common Mode	1.5 to 3.5 VDC	

(1) Measured as SIN(+) - SIN(-) or COS(+) - COS(-)




Figure 2-15: Sine Wave Encoder Phasing Reference Diagram




Figure 2-16: Sine Wave Encoder Schematic (Feedback Connector)

2.3.1.4. Encoder Phasing

Incorrect encoder polarity will cause the system to fault when enabled or when a move command is issued. Figure 2-17 illustrates the proper encoder phasing for clockwise motor rotation (or positive forcer movement for linear motors). To verify, move the motor by hand in the CW (positive) direction while observing the position of the encoder in the diagnostics display (see Figure 2-18).

For dual loop systems, the velocity feedback encoder is displayed in the diagnostic display (Figure 2-18).




Figure 2-17: Encoder Phasing Reference Diagram (Standard)



IMPORTANT: Encoder manufacturers may refer to the encoder signals as A, B, and Z. The proper phase relationship between signals is shown in Figure 2-17.




Figure 2-18: Position Feedback in the Diagnostic Display

2.3.2. Hall-Effect Inputs

The Hall-effect switch inputs are recommended for AC brushless motor commutation but not absolutely required. The Hall-effect inputs accept 5 VDC level signals. Hall states (0,0,0) or (1,1,1) are invalid and will generate a "Hall Fault" axis fault.

Refer to [Section 2.2.1.1](#), for Hall-effect device phasing.

Table 2-18: Hall-Effect Feedback Pins on the Feedback Connector

Pin #	Description	In/Out/Bi
3	+5V Power ⁽¹⁾	N/A
5	Hall-Effect Sensor B (brushless motors only)	Input
10	Hall-Effect Sensor A (brushless motors only)	Input
11	Hall-Effect Sensor C (brushless motors only)	Input
16	+5V Power ⁽¹⁾	N/A
20	Signal Common	N/A
21	Signal Common	N/A

(1) The maximum combined current output is 500 mA.




Figure 2-19: Hall-Effect Inputs Schematic (Feedback Connector)

2.3.3. Thermistor Input

The thermistor input is used to detect a motor over temperature condition by using a positive temperature coefficient sensor. As the temperature of the sensor increases, so does the resistance. Under normal operating conditions, the resistance of the thermistor is low which will result in a low input signal. As the increasing temperature causes the thermistor's resistance to increase, the sensor will trigger an over temperature fault.

The thermistor is connected between Pin 2 and Signal Common. The nominal trip value of the sensor is 1.385 k Ω . The circuit includes a 12 k Ω internal pull-up resistor which corresponds to a trip voltage of +0.52 V.

Table 2-19: Thermistor Input Pin on the Feedback Connector

Pin #	Description	In/Out/Bi
2	Motor Over Temperature Thermistor	Input




Figure 2-20: Thermistor Input Schematic (Feedback Connector)

2.3.4. Encoder Fault Input

The encoder fault input is for use with encoders that have a fault output. This is provided by some manufactures and indicates a loss of encoder function. The active state of this input is parameter configurable and the controller should be configured to disable the axis when the fault level is active. The nominal trip voltage of the encoder fault input is +2.5 V.

Table 2-20: Encoder Fault Input Pin on the Feedback Connector

Pin #	Description	In/Out/Bi
23	Encoder Fault Input	Input




Figure 2-21: Encoder Fault Input Schematic (Feedback Connector)

2.3.5. End of Travel and Home Limit Inputs

End of Travel (EOT) limits are required to define the end of the physical travel on linear axes. Positive or clockwise motion is stopped by the clockwise (CW) end of travel limit input. Negative or counterclockwise motion is stopped by the counterclockwise (CCW) end of travel limit input. The Home Limit switch can be parameter configured for use during the home cycle, however, the CW or CCW EOT limit is typically used instead. All of the end-of-travel limit inputs accept 0-5 VDC level signals. Limit directions are relative to the encoder polarity in the diagnostics display (refer to [Figure 2-24](#)).

Table 2-21: End of Travel and Home Limit Pins on the Feedback Connector

Pin #	Description	In/Out/Bi
12	Clockwise End of Travel Limit	Input
16	+5V Power	N/A
20	Signal Common	N/A
21	Signal Common	N/A
22	Home Switch Input	Input
24	Counterclockwise End of Travel Limit	Input

The active state (High/Low) of the EOT limits is software selectable (by the EndOfTravelLimitSetup axis parameter). [Figure 2-22](#) shows the possible wiring configurations for normally-open and normally-closed switches and the parameter setting to use for each configuration.



IMPORTANT: Use NPN-type normally-closed limit switches (Active High) to provide fail-safe behavior in the event of an open circuit.




Figure 2-22: End of Travel and Home Limit Input Connections




Figure 2-23: End of Travel and Home Limit Input Schematic (Feedback Connector)

2.3.5.1. End of Travel and Home Limit Phasing

If the EOT limits are reversed, you will be able to move further into a limit but be unable to move out. To correct this, swap the connections to the CW and CCW inputs at the Feedback connector or swap the CW and CCW limit functionality in the software using the EndOfTravelLimitSetup parameter. View the logic level of the EOT limit inputs in the Diagnostics display (shown in Figure 2-24).




Figure 2-24: End of Travel and Home Limit Input Diagnostic Display

2.3.6. Brake Outputs

The XL5e has a dedicated brake control circuit. Configure the brake with the BrakeSetup parameter for automatic control (typical). You can also use software commands to directly control the brake output.

Refer to [Section 2.6](#). for more information on powering the brake circuit.

Table 2-22: Brake Output Pins on the Feedback Connector

Pin #	Description	In/Out/Bi
13	Brake Output -	Output
25	Brake Output +	Output

Table 2-23: Brake Control Specifications

Specification	Value
Maximum Voltage	24 VDC
Maximum Current	1 A

A varistor must be connected across the brake to minimize voltage transients.




Figure 2-25: Brake Connected to the 25-Pin Feedback Connector (Typical)

2.4. Safe Torque Off Input (STO)

The STO circuit is comprised of two identical channels, each of which must be energized in order for the drive to produce motion. Each STO input is opto-isolated and accepts 24 V levels directly without the need for external current limiting resistors.



IMPORTANT: The drive might be equipped with an STO bypass circuit board. The bypass circuit board defeats the STO safety circuit and allows the system to run at all times. To use the STO safety functionality, remove the circuit board and make connections as outlined in this section.



IMPORTANT: The application circuit and its suitability for the desired safety level is the sole responsibility of the user of the drive.



WARNING: STO wires must be insulated to prevent short circuits between connector pins. The primary concern is a short circuit between STO 1 IN and STO 2 IN wire strands.

Table 2-24: STO Connector Pinout

Pin #	Signal	Description	In/Out/Bi	Connector
1	Power Supply +	Used to defeat STO by connecting to STO 1 IN and STO 2 IN	N/A	
2	STO 1 IN	STO Channel 1 Positive Input	Input	
3	RETURN	STO Negative Input	Input	
4	STO 2 IN	STO Channel 2 Positive Input	Input	
5	Power Supply -	Used to defeat STO by connecting to RETURN	N/A	

Table 2-25: Mating Connector Part Numbers for the STO Connector

Description	Aerotech P/N	Phoenix P/N	Tightening Torque (Nm)	Wire Size: AWG [mm ²]
5-Pin Terminal Block	ECK02393	1827622	0.22 - 0.25	2.5 - 0.05 [14-30]

Table 2-26: STO Electrical Specifications

Status	Value
STO off (motion allowed)	18-24 V, 7 ma
STO on (safe state entered, no motion)	0-6 V
Recommended Wire Gauge	22-26 AWG (0.5 - 0.14 mm ²)
STO System Power Supply	PELV
STO Wire Length (maximum)	50 m

Figure 2-26 shows one safety device connected to multiple drives in parallel.



WARNING: The drive does not check for short circuits on the external STO wiring. If this is not done by the external safety device, short circuits on the wiring must be excluded. Refer to EN ISO 13849-2. For Category 4 systems, the exclusion of short circuits is mandatory.




Figure 2-26: Typical Configuration

2.4.1. STO Standards

Table 2-27 describes and specifies the safety requirements at the system level for the Safe Torque Off (STO) feature of the drive. This assumes that diagnostic testing is performed according to Section 2.4.4. and Table 2-28.

Table 2-27: STO Standards

Standard	Maximum Achievable Safety
EN/IEC 61800-5- 2:2016	SIL 3
EN/IEC 61508-1:2010	SIL 3
EN/IEC 61508-2:2010	SIL 3
EN ISO 13849-1:2015	Category 4, PL e
EN/IEC 62061:2005 with Amendments	SIL 3

Table 2-28: STO Standards Data

Standard	Value
EN ISO 13849-1:2015	MTTF _D > 1000 years, DC _{AVG} 99% Maximum PL e, Category 4
EN ISO 13849-1:2015 EN/IEC 61508	Lifetime = 20 years No proof test required Interval for manual STO test: <ul style="list-style-type: none"> Once per year for SIL2/PL d/category 3 Once per three months for SIL3/PL e/category 3 Once per day for SIL3/PL e/category 4
EN/IEC 61508	SIL3 PFH < 3 FIT SFF > 99%

2.4.2. STO Functional Description

The motor can only be activated when voltage is applied to both STO 1 and STO 2 inputs. The STO state will be entered if power is removed from either the STO 1 or the STO 2 inputs. When the STO state is entered, the motor cannot generate torque or force and is therefore considered safe.

The STO function is implemented with two redundant channels in order to meet stated performance and SIL levels. STO 1 disconnects the high side power amplifier transistors and STO 2 disconnects the low side power amplifier transistors. Disconnecting either set of transistors effectively prevents the drive from being able to produce motion.

The drive software monitors each STO channel and will generate an Emergency Stop software fault when either channel signals the stop state. Each STO channel contains a fixed delay which allows the drive to perform a controlled stop before the power amplifier transistors are turned off.

A typical configuration requiring a controlled stop has the Emergency Stop Fault mask bit set in the FaultMask, FaultMaskDecel, and FaultMaskDisable parameters. This stops the axis using the rate specified by the AbortDecelRate parameter. The software will disable the axis as soon as the deceleration ramp is complete. This is typically configured to occur before the STO channel turns off the power amplifier transistors.

The software controlled stop functionality must be excluded when considering overall system safety. This is because the software is not safety rated and cannot be included as part of the safety function.

The drive will tolerate short diagnostic pulses on the STO 1+ and STO 2+ inputs. The parameter "STOPulseFilter" specifies the maximum pulse width that the drive will ignore.

To resume normal operation, apply power to both STO 1 and STO 2 inputs and use the *Acknowledge All* button or the AcknowledgeAll() or FaultAcknowledge() function to clear the Emergency Stop software fault. The recommended use of the Emergency Stop Fault fault mask bits prevent the system from automatically restarting.

You can achieve longer delay times through the use of an external delay timer, such as the Omron G9SA-321 Safety Relay Unit. Place this device between the system ESTOP wiring and the drive's STO inputs. Connect the ESTOP signal directly to a digital input, in addition to the external timer, to allow the drive to begin a software-controlled stop as soon as the ESTOP signal becomes active. Use the EmergencyStopFaultInput parameter to configure a digital input as an ESTOP input.

Non-standard STO delay times are provided by special factory order. In this case, the non-standard STO delay time is indicated by a label placed on the slice amplifier's main connector (STO DELAY = xx sec).

Table 2-29: STO Signal Delay

	Value
STO Time Delay	450-550 msec

Table 2-30: Motor Function Relative to STO Input State

STO 1	STO 2	Motor Function
Unpowered	Unpowered	No force/torque
Unpowered ⁽¹⁾	Powered ⁽¹⁾	No force/torque
Powered ⁽¹⁾	Unpowered ⁽¹⁾	No force/torque
Powered	Powered	Normal Operation

1. This is considered a Fault Condition since STO 1 and STO 2 do not match. Refer to [Section 2.4.4](#).

2.4.3. STO Startup Validation Testing

Verify the state of the STO 1 and STO 2 channels by manually activating the external STO hardware. Each STO channel must be tested separately in order to detect potential short circuits between the channels. The current state of the STO 1 and STO 2 inputs is shown in the Status Utility. A “-” indicates that the STO input is powered by a high voltage level (24 V). An “ON” indicates that the voltage source has been removed from the input (open circuit or 0 V), and that the STO channel is in the safe state.



DANGER: The STO circuit does not remove lethal voltage from the motor terminals. AC mains power must be removed before servicing.

2.4.4. STO Diagnostics

Activation of STO means removing power from the drive's STO inputs. This is typically done by pressing the emergency stop switch. The drive initiates a diagnostic check every time the STO is activated after the Diagnostic Test Delay Time has elapsed. The diagnostic check verifies that each channel has entered the safe state. The drive is held in the safe state if it determines that one of the channels has not properly entered the safe state. An open circuit or short to 24 V in either STO channel will result in this condition (refer to Section 2.4.3.). The Status Utility screen can be used to verify the levels of the STO input signals while trouble shooting.

In order to meet the listed SIL level, the STO circuit must be activated (power removed from both inputs) according to the interval specified in Table 2-28.

Table 2-31: STO Timing

Time	Description	Value
T1	STO Delay Time (STO input active to motor power off)	450-550 msec
T2	STO deactivated to motor power on (the software is typically configured so that the motor does not automatically re-energize).	< 1 msec
T3	Diagnostic Test Delay Time	550-610 msec





Figure 2-27: STO Timing

The software is typically configured to execute a controlled stop when the STO state is first detected. If power is reapplied to the STO inputs before the STO Delay Time, an STO hardware shutdown will not occur but a software stop may, depending on the width of the STO pulse. The controller will ignore STO active pulses shorter in length than the STOPulseFilter parameter setting.

2.5. Auxiliary I/O Connector

The Auxiliary I/O connector has 1 analog input, 6 digital inputs, 1 analog output, 4 digital outputs, a secondary line driver encoder input, and a secondary absolute encoder interface.

Table 2-32: Auxiliary I/O Connector Pinout

Pin#	Description	In/Out/Bi	Connector
1	Auxiliary Sine +	Bidirectional	
	Absolute Encoder Data +	Bidirectional	
2	Auxiliary Sine -	Bidirectional	
	Absolute Encoder Data -	Bidirectional	
3	High-Speed Input 20 + / PSO External Sync. +	Input	
4	High-Speed Input 20 - / PSO External Sync. -	Input	
5	High-Speed Input 21 +	Input	
6	High-Speed Input 21 -	Input	
7	Digital Output 0	Output	
8	Digital Output 1	Output	
9	Digital Output 2	Output	
10	Auxiliary Cosine +	Bidirectional	
	Absolute Encoder Clock +	Output	
11	Auxiliary Cosine-	Bidirectional	
	Absolute Encoder Clock -	Output	
12	+5 Volt (500 mA max)	N/A	
13	Analog Input 0+ (Differential)	Input	
14	Analog Input 0- (Differential)	Input	
15	Digital Output Common	N/A	
16	Digital Output 3	Output	
17	Digital Input 0 / CCW EOT Input ⁽¹⁾	Input	
18	Digital Input 1 / CW EOT Input ⁽¹⁾	Input	
19	Auxiliary Marker- / PSO output ⁽²⁾ / TTL Output	Bidirectional	
20	Auxiliary Marker+ / PSO output ⁽²⁾	Bidirectional	
21	Common	N/A	
22	Analog Output 0	Output	
23	Analog Common	N/A	
24	Digital Input Common	N/A	
25	Digital Input 2 / Home Input ⁽¹⁾	Input	
26	Digital Input 3	Input	

(1) Software configured option
(2) For PSO, refer to [Section 2.5.2](#).

Table 2-33: Mating Connector Part Numbers for the Auxiliary I/O Connector

Mating Connector	Aerotech P/N	Third Party P/N
Connector	ECK01259	Kycon K86-AA-26P
Backshell	ECK01022	Amphenol 17-1725-2

NOTE: These items are provided as a set under the Aerotech P/N: MCK-26HDD.

2.5.1. Auxiliary Encoder Inputs

The Auxiliary Encoder connector gives you a second encoder input channel. This channel is typically used for dual loop applications.

Use the AuxiliaryFeedbackType parameter to configure the XL5e to accept an encoder signal type.

Square Wave encoder signals: [Section 2.5.1.1.](#)

Absolute encoder signals: [Section 2.5.1.2.](#)

Sine Wave encoder signals (with the -MX3 option): [Section 2.5.1.3.](#)

You can configure the Auxiliary Encoder interface as an output that will transmit encoder signals for external use. Use the DriveEncoderOutputConfigureInput() function to configure the Sine \pm and Cosine \pm connector pins as RS-422 outputs. You can only echo incremental square wave primary encoder inputs or, with the -MX2 or -MX3 option, incremental sine wave primary encoder inputs. You cannot use the absolute encoder interface when you echo incremental signals.

Table 2-34: Auxiliary Encoder Pins on the Auxiliary I/O Connector

Pin#	Description	In/Out/Bi
1	Auxiliary Sine +	Bidirectional
	Absolute Encoder Data +	Bidirectional
2	Auxiliary Sine -	Bidirectional
	Absolute Encoder Data -	Bidirectional
10	Auxiliary Cosine +	Bidirectional
	Absolute Encoder Clock +	Output
11	Auxiliary Cosine-	Bidirectional
	Absolute Encoder Clock -	Output
12	+5 Volt (500 mA max)	N/A
19	Auxiliary Marker- / PSO output ⁽²⁾ / TTL Output	Bidirectional
20	Auxiliary Marker+ / PSO output ⁽²⁾	Bidirectional
21	Common	N/A

(2) For PSO, refer to [Section 2.5.2.](#)

2.5.1.1. Square Wave Encoder

The drive accepts RS-422 square wave encoder signals. The drive will generate a feedback fault if it detects an invalid signal state caused by an open or shorted signal connection. Use twisted-pair wiring for the highest performance and noise immunity.

Table 2-35: Square Wave Encoder Specifications

Specification	Value
Encoder Frequency	10 MHz maximum (25 ns minimum edge separation)
x4 Quadrature Decoding	40 million counts/sec




Figure 2-28: Square Wave Encoder Interface (Aux I/O Connector)

2.5.1.2. Absolute Encoder

The drive retrieves absolute position data along with encoder fault information through a serial data stream from the absolute encoder. Use twisted-pair wiring for the highest performance and noise immunity. You cannot use an absolute encoder with incremental signals on the Auxiliary I/O Connector.

Refer to [Figure 2-29](#) for the serial data stream interface.

Refer to the Help file for information on how to set up your EnDat or BiSS absolute encoder parameters.




Figure 2-29: Absolute Encoder Schematic (Auxiliary I/O Connector)

2.5.1.3. Sine Wave Encoder [-MX3 Option]

The Sine Wave Encoder option provides higher positioning resolution by subdividing the fundamental output period of the encoder into smaller increments. The amount of subdivision is specified by the AuxiliaryEncoderMultiplicationFactor parameter. Use Encoder Tuning to adjust the value of the gain, offset, and phase balance controller parameters to get the best performance. For more information, refer to the Help file.

You cannot use the sine wave encoder on the auxiliary connector with the -MX3 multiplier option as an input to the PSO. The -MX3 option does not generate emulated quadrature signals from the auxiliary connector.

For the highest performance, use twisted pair double-shielded cable with the inner shield connected to signal common and the outer shield connected to frame ground. Do not join the inner and outer shields in the cable.

Table 2-36: Sine Wave Encoder Specifications

Specification	Value	
	Primary	Auxiliary
Input Frequency (max)	450 kHz, 2 MHz	450 kHz
Input Amplitude ⁽¹⁾	0.6 to 1.75 V _{pk-pk}	
Interpolation Factor (max)	-MX2	65,536
	-MX3	65,536
-MX2/-MX3 Primary Encoder Channel Interpolation Latency	800 nsec (analog input to quadrature output)	
Input Common Mode	1.5 to 3.5 VDC	

(1) Measured as SIN(+) - SIN(-) or COS(+) - COS(-)




Figure 2-30: Sine Wave Encoder Phasing Reference Diagram




Figure 2-31: Sine Wave Encoder Schematic (Auxiliary I/O Connector)

2.5.2. Position Synchronized Output (PSO)

The PSO signal is available on the dual-function AUX Marker/PSO signal lines. Use the PSO pulse external sync functions to configure the auxiliary marker as an output. Refer to the Help file for more information.

Use the `PsoOutputConfigureOutput()` function to transmit the PSO output signal on the Marker \pm pins differentially. Or, use the `PsoOutputConfigureOutput()` function to configure the Marker - pin as a 5V TTL PSO output.

The differential signal format is recommended when using long cable lengths in noisy environments or when high frequency pulse transmission is required. It is best to locate the line receiver close to the receiving electronics. A 5 V TTL signal is used to drive an opto coupler or general purpose TTL input. This signal is active high and is driven to 5 V when a PSO fire event occurs. When the drive is reset or after initial power up, the PSO pins (refer to [Table 2-38](#)), are not actively driven and the fail safe state is defined by pull-up and pull-down resistors as shown in [Figure 2-32](#).

The -EB1 I/O option board has additional PSO signal formats. Refer to [Section 3.5](#). for more information.

Table 2-37: PSO Specifications

Specification		Value
Output	TTL	5 V, 16 mA (max)
Maximum PSO Output (Fire) Frequency	TTL	12.5 MHz
	RS-422	12.5 MHz
Output Latency [Fire event to output change]	TTL	15 ns
	RS-422	15 ns

Table 2-38: PSO Pins on the Auxiliary I/O Connector

Pin#	Description	In/Out/Bi
19	Auxiliary Marker- / PSO output / TTL Output	Bidirectional
20	Auxiliary Marker+ / PSO output	Bidirectional
21	Common	N/A




Figure 2-32: PSO Interface

2.5.3. Digital Outputs

Optically-isolated solid-state relays drive the digital outputs. You can connect the digital outputs in current sourcing or current sinking mode but you must connect all four outputs in the same configuration. Refer to [Figure 2-34](#) and [Figure 2-35](#).

You must install suppression diodes on digital outputs that drive relays or other inductive devices. To see an example of a current sourcing output that has diode suppression, refer to [Figure 2-34](#). To see an example of a current sinking output that has diode suppression, refer to [Figure 2-35](#).

The digital outputs are not designed for high-voltage isolation applications and they should only be used with ground-referenced circuits.

The digital outputs have overload protection. They will resume normal operation when the overload is removed.

Table 2-39: Digital Output Specifications

Digital Output Specifications	Value
Maximum Voltage	24 V (26 V Maximum)
Maximum Sink/Source Current	250 mA/output
Output Saturation Voltage	0.9 V at maximum current
Output Resistance	3.7 Ω
Rise / Fall Time	250 μ s (2K pull up to 24V)
Reset State	Output Off (High Impedance State)

Table 2-40: Digital Output Pins on the Auxiliary I/O Connector

Pin#	Description	In/Out/Bi
7	Digital Output 0	Output
8	Digital Output 1	Output
9	Digital Output 2	Output
15	Digital Output Common	N/A
16	Digital Output 3	Output




Figure 2-33: Digital Output Schematic (Aux I/O Connector)




Figure 2-34: Digital Outputs Connected in Current Sourcing Mode




Figure 2-35: Digital Outputs Connected in Current Sinking Mode

2.5.4. Digital Inputs

You can connect the digital inputs to current sourcing or current sinking devices but you must connect all four inputs in the same configuration. Refer to [Figure 2-37](#) and [Figure 2-38](#). The digital inputs are not designed for high-voltage isolation applications. They should only be used with ground-referenced circuits.

Table 2-41: Digital Input Specifications

Input Voltage	Approximate Input Current	Turn On Time	Turn Off Time
+5 V to +24 V	6 mA	10 μ s	43 μ s

Table 2-42: Digital Input Pins on the Auxiliary I/O Connector

Pin#	Description	In/Out/Bi
17	Digital Input 0 / CCW EOT Input ⁽¹⁾	Input
18	Digital Input 1 / CW EOT Input ⁽¹⁾	Input
24	Digital Input Common	N/A
25	Digital Input 2 / Home Input ⁽¹⁾	Input
26	Digital Input 3	Input

(1) Software configured option




Figure 2-36: Digital Inputs Schematic (Aux I/O Connector)




Figure 2-37: Digital Inputs Connected to Current Sourcing Devices




Figure 2-38: Digital Inputs Connected to Current Sinking Devices

2.5.5. High-Speed Inputs

High-speed inputs 20 and 21 can be used as general purpose inputs or as the trigger signal for high speed data collection. Refer to the DriveDataCaptureConfigureTrigger() function topic in the Help file for more information.

You can use the external PSO synchronization functions to synchronize waveform generation with an external synchronization signal. When you activate this feature, the PSO Waveform module will not generate the configured waveform when an output event is received until the rising edge of the synchronization signal occurs.

Table 2-43: High-Speed Input Specifications

Specification	Value
Input Voltage	5V - 24 V input voltages
Input Current	10 mA
Input Device	HCPL-0630
Delay	50 nsec

Table 2-44: High-Speed Input Pins on the Auxiliary I/O Connector

Pin#	Description	In/Out/Bi
3	High-Speed Input 20 + / PSO External Sync. +	Input
4	High-Speed Input 20 - / PSO External Sync. -	Input
5	High-Speed Input 21 +	Input
6	High-Speed Input 21 -	Input




Figure 2-39: High-Speed Inputs

2.5.6. Analog Output 0

The analog output can be set from within a program or it can be configured to echo the state of select servo loop nodes.

The analog output is set to zero when you power on the system or reset the drive.

Table 2-45: Analog Output Specifications

Specification	Value
Output Voltage	-10 V to +10 V
Output Current	5 mA
Resolution (bits)	16 bits

Table 2-46: Analog Output Pins on the Auxiliary I/O Connector

Pin#	Description	In/Out/Bi
22	Analog Output 0	Output
23	Analog Common	N/A




Figure 2-40: Analog Output 0 Schematic

2.5.7. Analog Input 0 (Differential)

To interface to a single-ended, non-differential voltage source, connect the signal common of the source to the negative input and connect the analog source signal to the positive input. A floating signal source must be referenced to the analog common. Refer to Figure 2-41.

Table 2-47: Analog Input Specifications

Specification	Value
(AI+) - (AI-)	+10 V to -10 V ⁽¹⁾
Resolution (bits)	16 bits
Input Impedance	1 MΩ
1. Signals outside of this range may damage the input	

Table 2-48: Analog Input Pins on the Auxiliary I/O Connector

Pin#	Description	In/Out/Bi
13	Analog Input 0+ (Differential)	Input
14	Analog Input 0- (Differential)	Input
23	Analog Common	N/A




Figure 2-41: Analog Input 0 Schematic

2.6. Brake Power Supply Connector

This port is the power supply connection to the on-board brake control circuit. Refer to [Section 2.3.6](#) for more information about the brake output interface.

Table 2-49: Brake Power Supply Connector Pinout

Pin#	Description	In/Out/Bi	Connector
1	Brake Power Supply (+)	Input	
2	Brake Power Supply (-)	Input	

Table 2-50: Mating Connector Part Numbers for the Brake Power Supply Connector

Description	Aerotech P/N	Phoenix P/N	Tightening Torque (Nm)	Wire Size: AWG [mm ²]
2-Pin Terminal Block	ECK02390	1827616	0.22 - 0.25	0.14 - 1.5 [26-16]

2.7. HyperWire Interface

The HyperWire bus is the high-speed communications connection from the controller. It operates at 2 gigabits per second. The controller sends all command and configuration information through the HyperWire bus.

HyperWire cables can be safely connected to or disconnected from a HyperWire port while the PC and/or drive is powered on. However, any changes to the HyperWire network topology will disrupt communication and you must reset the controller to re-establish communication.



WARNING: Do not connect or disconnect HyperWire cables while you are loading firmware or damage to the drives may occur.

Table 2-51: HyperWire Card Part Number

Part Number	Description
HYPERWIRE-PCIE	HyperWire adapter, PCIe x4 interface

Table 2-52: HyperWire Cable Part Numbers

Part Number	Description
HYPERWIRE-AO10-5	HyperWire cable, active optical, 0.5 m
HYPERWIRE-AO10-10	HyperWire cable, active optical, 1.0 m
HYPERWIRE-AO10-30	HyperWire cable, active optical, 3.0 m
HYPERWIRE-AO10-50	HyperWire cable, active optical, 5.0 m
HYPERWIRE-AO10-200	HyperWire cable, active optical, 20.0 m

2.8. Sync Port

The Sync port is a bi-directional high speed proprietary interface that lets you transmit encoder signals between drives. This is typically used for multi-axis PSO applications where one or two drives send their encoder signals to a main drive that has the PSO logic and PSO output signal. The XL5e contains two Sync ports, labeled A and B.

To avoid signal contention, all Sync ports default to the input state during reset and immediately after power is applied to the drive.

Table 2-53: Sync-Related Functions

Function	Description
DriveEncoderOutputConfigureDivider(), DriveEncoderOutputConfigureInput(), DriveEncoderOutputOn(), DriveEncoderOutputOff()	Configure each Sync port as an input or an output
PsoDistanceConfigureInputs()	Let the PSO to track the SYNC A or SYNC B port.
PsoWindowConfigureInput()	

The Sync port uses low-voltage differential signaling (LVDS) and standard USB 3.0 type A (cross over) cables.

Table 2-54: Sync Port Cables

Part Number	Description
CBL-SYNC-3	Length 3 dm; Connectors: USB Type A to USB Type A
CBL-SYNC-5	Length 5 dm; Connectors: USB Type A to USB Type A
CBL-SYNC-7	Length 7 dm; Connectors: USB Type A to USB Type A
CBL-SYNC-10	Length 10 dm; Connectors: USB Type A to USB Type A

2.9. System Interconnection





Figure 2-42: System Wiring Drawing (Best Practice)



<p>! ATTENTION !</p> <p>The system integrator or end user is responsible for all safety compliance and technical requirements for the system wiring.</p>	<p>System Protective Earth (PE) grounds</p> <ul style="list-style-type: none"> Keep PE wires as short as possible Each PE wire should have a dedicated attach/termination point Aerotech recommends that you should terminate each PE directly to the grounded component panel. Refer to Note 1 above. 	<p>Axis FEEDBACK cable Ferrite EMC filters</p> <ul style="list-style-type: none"> PN: Fair-Rite #0446167281 (Aerotech # EC202348) Clamp-On Construction Apply as close as possible to the FEEDBACK connector as illustrated
<p>IMPORTANT: Read all parts of this manual before you install or operate the XL5e or before you do maintenance to your system.</p> <ul style="list-style-type: none"> To prevent injury to you and damage to the equipment, obey the precautions in this manual. If you do not understand the information in this manual, contact Aerotech Global Technical Support. 	<p>XL5e Controllers</p> <ul style="list-style-type: none"> Refer to assemblies (A1), (A2), and (A3) If the controllers were purchased as an integrated system, refer to the System Interconnectors drawing included with the system documentation. Note that a controller's serial number is specific to an assigned axis. 	<p>XL5e Controller Control Power and UFM-ST Ferrite EMC Filters</p> <ul style="list-style-type: none"> PN: Fair-Rite #0446164281 (Aerotech # EC202347) Clamp-On Construction Apply as close as possible to the power connector as illustrated
<p>For EMC performance, mount all system components on to a common conductive metal panel.</p> <ul style="list-style-type: none"> Do not use a panel that has a painted or non-conductive coat applied. You can use a panel with a conductive surface coat. 	<p>Connect the system motor cable directly to the controller MOTOR OUTPUT terminals</p>	<p>System AC Supply Ferrite EMC Filter</p> <ul style="list-style-type: none"> PN: Laird ALFB360330-300 (Aerotech # EC202398) Torus-Ring Construction Loop System AC1 and AC2 conductor pair two times through the toroid
<p>Customer-supplied wiring</p> <ul style="list-style-type: none"> The system integrator is responsible for all safety compliance and technical requirements. Aerotech recommends that you use AC1 & AC2 twisted pair conductors with circuit runs as short as possible. When routing conductors, keep high-voltage supply wiring separated from low-voltage I/O or control/feedback signal wiring. 	<p>UFM-ST (Filter, AC Line) Enclosure</p> <ul style="list-style-type: none"> Refer to assemblies (A4) and (A5) For mechanical and electrical descriptions of the UFM-ST, refer to the UFM-ST Hardware Manual (UFM-ST.pdf) at http://www.aerotechmotioncontrol.com/manuals/index.aspx. Find the manual under the Controller Accessories dropdown. 	<p>System AC Power</p> <ul style="list-style-type: none"> If AC2 is not referenced to NEUTRAL, the AC2 line must have a fuse or circuit breaker protection

The information on this page is for reference only and represents best practice applications.

Figure 2-43: System Interconnection Drawing (Best Practice)

2.10. PC Configuration and Operation Information

For more information about hardware requirements, PC configuration, programming, system operation, and utilities, refer to the Help file.

This page intentionally left blank.

Chapter 3: -EB1 I/O Option Board

The -EB1 I/O option board has 16 digital inputs, 16 digital outputs, 3 analog inputs, 3 analog outputs, and PSO outputs.




Figure 3-1: XL5e with -EB1 I/O Option Board Connectors

3.1. Digital Outputs [-EB1]

Optically-isolated solid-state relays drive the digital outputs. You can connect the digital outputs in current sourcing or current sinking mode but you must connect all four outputs in a port in the same configuration. Refer to [Figure 3-3](#) and [Figure 3-4](#).

The digital outputs are not designed for high-voltage isolation applications and they should only be used with ground-referenced circuits.

You must install suppression diodes on digital outputs that drive relays or other inductive devices. To see an example of a current sourcing output that has diode suppression, refer to [Figure 3-3](#). To see an example of a current sinking output that has diode suppression, refer to [Figure 3-4](#).

The digital outputs have overload protection. They will resume normal operation when the overload is removed.

Table 3-1: Digital Output Specifications [-EB1]

Digital Output Specifications	Value
Maximum Voltage	24 V (26 V Maximum)
Maximum Sink/Source Current	250 mA/output
Output Saturation Voltage	0.9 V at maximum current
Output Resistance	3.7 Ω
Rise / Fall Time	250 μ s (2K pull up to 24V)
Reset State	Output Off (High Impedance State)

Table 3-2: Digital Output 1 Connector Pinout [-EB1]


Pin#	Description	In/Out/Bi	Connector
1	Output Common for Outputs 4-7	N/A	
2	Output 4 (Optically-Isolated)	Output	
3	Output 5 (Optically-Isolated)	Output	
4	Output 6 (Optically-Isolated)	Output	
5	Output 7 (Optically-Isolated)	Output	
6	Output Common for Outputs 8-11	N/A	
7	Output 8 (Optically-Isolated)	Output	
8	Output 9 (Optically-Isolated)	Output	
9	Output 10 (Optically-Isolated)	Output	
10	Output 11 (Optically-Isolated)	Output	

Table 3-3: Mating Connector Part Numbers for the Digital Output 1 Connector [-EB1]

Mating Connector	Aerotech P/N	Third Party P/N	Wire Size: mm ² [AWG]
10-Pin Terminal Block	ECK02395	Phoenix 1700841	0.5 - 0.14 [20-26]

Table 3-4: Digital Output 2 Connector Pinout [-EB1]


Pin#	Description	In/Out/Bi	Connector
1	Output Common for Outputs 12-15	N/A	
2	Output 12 (Optically-Isolated)	Output	
3	Output 13 (Optically-Isolated)	Output	
4	Output 14 (Optically-Isolated)	Output	
5	Output 15 (Optically-Isolated)	Output	
6	Output Common for Outputs 16-19	N/A	
7	Output 16 (Optically-Isolated)	Output	
8	Output 17 (Optically-Isolated)	Output	
9	Output 18 (Optically-Isolated)	Output	
10	Output 19 (Optically-Isolated)	Output	

Table 3-5: Mating Connector Part Numbers for the Digital Output 2 Connector [-EB1]

Mating Connector	Aerotech P/N	Third Party P/N	Wire Size: mm ² [AWG]
10-Pin Terminal Block	ECK02395	Phoenix 1700841	0.5 - 0.14 [20-26]






Figure 3-2: Digital Outputs Schematic [-EB1]



DIODE REQUIRED ON EACH OUTPUT THAT DRIVES AN INDUCTIVE DEVICE (COIL), SUCH AS A RELAY.

Figure 3-3: Digital Outputs Connected in Current Sourcing Mode [-EB1]



DIODE REQUIRED ON EACH OUTPUT THAT DRIVES AN INDUCTIVE DEVICE (COIL), SUCH AS A RELAY.

Figure 3-4: Digital Outputs Connected in Current Sinking Mode [-EB1]

3.2. Digital Inputs [-EB1]

Input bits are arranged in groups of 4 and each group shares a common pin. This lets a group be connected to current sourcing or current sinking devices, based on the connection of the common pin in that group.

To be able to connect an input group to current sourcing devices, connect the input group's common pin to the power supply return (-). Refer to [Figure 3-6](#).

To be able to connect an input group to current sinking devices, connect the input group's common pin to the power supply source (+). Refer to [Figure 3-7](#).

The digital inputs are not designed for high-voltage isolation applications. They should only be used with ground-referenced circuits.

Table 3-6: Digital Input Specifications [-EB1]

Input Voltage	Approximate Input Current	Turn On Time	Turn Off Time
+5 V to +24 V	6 mA	10 μ s	43 μ s

Table 3-7: Digital Input 1 Connector Pinout [-EB1]


Pin#	Description	In/Out/Bi	Connector
1	Input Common for Inputs 4-7	N/A	
2	Input 4 (Optically-Isolated)	Input	
3	Input 5 (Optically-Isolated)	Input	
4	Input 6 (Optically-Isolated)	Input	
5	Input 7 (Optically-Isolated)	Input	
6	Input Common for Inputs 8-11	N/A	
7	Input 8 (Optically-Isolated)	Input	
8	Input 9 (Optically-Isolated)	Input	
9	Input 10 (Optically-Isolated)	Input	
10	Input 11 (Optically-Isolated)	Input	

Table 3-8: Mating Connector Part Numbers for the Digital Input 1 Connector [-EB1]

Mating Connector	Aerotech P/N	Third Party P/N	Wire Size: mm ² [AWG]
10-Pin Terminal Block	ECK02395	Phoenix 1700841	0.5 - 0.14 [20-26]

Table 3-9: Digital Input 2 Connector Pinout [-EB1]


Pin#	Description	In/Out/Bi	Connector
1	Input Common for Inputs 12-15	N/A	
2	Input 12 (Optically-Isolated)	Input	
3	Input 13 (Optically-Isolated)	Input	
4	Input 14 (Optically-Isolated)	Input	
5	Input 15 (Optically-Isolated)	Input	
6	Input Common for Inputs 16-19	N/A	
7	Input 16 (Optically-Isolated)	Input	
8	Input 17 (Optically-Isolated)	Input	
9	Input 18 (Optically-Isolated)	Input	
10	Input 19 (Optically-Isolated)	Input	

Table 3-10: Mating Connector Part Numbers for the Digital Input 2 Connector [-EB1]

Mating Connector	Aerotech P/N	Third Party P/N	Wire Size: mm ² [AWG]
10-Pin Terminal Block	ECK02395	Phoenix 1700841	0.5 - 0.14 [20-26]




Figure 3-5: Digital Inputs Schematic [-EB1]



IMPORTANT: Each bank of four inputs must be connected in an all sourcing or all sinking configuration.




Figure 3-6: Digital Inputs Connected to Current Sourcing (PNP) Devices [-EB1]




Figure 3-7: Digital Inputs Connected to Current Sinking (NPN) Devices [-EB1]

3.3. Analog Outputs [-EB1]

The analog outputs can be set from within a program or they can be configured to echo the state of select servo loop nodes.

The analog outputs are set to zero when you power on the system or reset the drive.

Table 3-11: Analog Output Specifications [-EB1]

Specification	Value
Output Voltage	-10 V to +10 V
Output Current	5 mA
Resolution (bits)	16 bits

Table 3-12: Analog Output Connector Pinout [-EB1]


Pin #	Description	In/Out/Bi	Connector
1	Analog Output 1	Output	
2	Analog Output 2	Output	
3	Analog Output 3	Output	
4	Ground	N/A	

Table 3-13: Mating Connector Part Numbers for the Analog Output Connector [-EB1]

Type	Aerotech P/N	Third Party P/N	Wire Size: mm ² [AWG]
4-Pin Terminal Block	ECK02399	Phoenix 1768004	0.5- 0.14 [20-26]




Figure 3-8: Analog Output Typical Connection [-EB1]

3.4. Analog Inputs [-EB1]

To interface to a single-ended, non-differential voltage source, connect the signal common of the source to the negative input and connect the analog source signal to the positive input. A floating signal source must be referenced to the analog common. Refer to [Figure 3-9](#).

Table 3-14: Differential Analog Input Specifications [-EB1]

Specification	Value
(AI+) - (AI-)	+10 V to -10 V ⁽¹⁾
Resolution (bits)	16 bits
Input Impedance	1 MΩ
1. Signals outside of this range may damage the input	

Table 3-15: Analog Input Connector Pinout [-EB1]

Pin#	Description	In/Out/Bi	Connector
1	+5V (250 mA max)	N/A	
2	Analog Input 1+	Input	
3	Analog Input 1-	Input	
4	Analog Input 2+	Input	
5	Analog Input 2-	Input	
6	Analog Input 3+	Input	
7	Analog Input 3-	Input	
8	Ground	N/A	

Table 3-16: Mating Connector Part Numbers for the Analog Input Connector [-EB1]

Mating Connector	Aerotech P/N	Third Party P/N	Wire Size: mm ² [AWG]
8-Pin Terminal Block	ECK02397	Phoenix 1908101	0.5 - 0.14 [20-26]




Figure 3-9: Analog Input Typical Connection [-EB1]

3.5. Position Synchronized Output Interface [-EB1]

The PSO output signal is available on the -EB1 option board in two signal formats: TTL and Isolated.

The PSO signal is also available on the AUX I/O connector. Refer to [Section 2.5.2](#).

Table 3-17: PSO Specifications [-EB1]

Specification		Value
Output	TTL	5 V, 16 mA (max)
	Isolated	5-24 V, 250 mA
Maximum PSO Output (Fire) Frequency	TTL	12.5 MHz
	Isolated	5 MHz
Output Latency [Fire event to output change]	TTL	5 ns
	Isolated	150 ns

Table 3-18: PSO Interface Connector Pinout [-EB1]


Pin #	Description	In/Out/Bi	Connector
1	PSO Output+	Output	
2	PSO Output-	Output	
3	PSO Output (TTL)	Output	
4	Ground	N/A	

Table 3-19: Mating Connector Part Numbers for the PSO Interface Connector [-EB1]

Type	Aerotech P/N	Third Party P/N	Wire Size: mm ² [AWG]
4-Pin Terminal Block	ECK02399	Phoenix 1768004	0.5- 0.14 [20-26]

Isolated Signals

This output signal is a fully-isolated 5-24V compatible output capable of sourcing or sinking current. This output is normally open and only conducts current when a PSO fire event occurs.

The PSO Isolated Outputs are overload protected and will turn off if the maximum output current is exceeded.




Figure 3-10: PSO Output Sources Current




Figure 3-11: PSO Output Sinks Current

TTL Signals

This output signal is a 5V TTL signal which is used to drive an opto coupler or general purpose TTL input. This signal is active high and is driven to 5V when a PSO fire event occurs.




Figure 3-12: PSO TTL Outputs Schematic

Chapter 4: Cables and Accessories



IMPORTANT: Find Aerotech cable drawings on the website at <http://www.aerotechmotioncontrol.com/manuals/index.aspx>.

Table 4-1: Standard Interconnection Cables

Cable Part #	Description
Joystick	Refer to Section 4.1 .
ECZ01231	BBA32 Interconnect Cable

4.1. Joystick Interface

Aerotech Multi-Axis Joystick (NEMA12 (IP54) rated) is powered from 5 V and has a nominal 2.5 V output in the center detent position. Three buttons are used to select axis pairs and speed ranges. An optional interlock signal is used to indicate to the controller that the joystick is present. Joystick control will not activate unless the joystick is in the center location. Third party devices can be used provided they produce a symmetric output voltage within the range of -10 V to +10 V.

Connecting joystick with an Aerotech cable, all Aerotech cables are labeled to identify the connector and connections. The joystick parameters must be set to match the analog and digital I/O connections.

The following drawings illustrate how to connect a single- or two-axis joystick. Refer to the Help file for programming information about how to change joystick parameters.




Figure 4-1: Two Axis Joystick Interface (to the Aux I/O of two drives)




Figure 4-2: Two Axis Joystick Interface (to the I/O board)

4.2. Handwheel Interface

A handwheel can be used to manually control axis position. The handwheel must provide 5V differential quadrature signals to the drive.



IMPORTANT: You can find instructions on how to enable the handwheel in the Help file.

Connect a handwheel to the Aux I/O as shown in Figure 4-3 or Figure 4-4.




Figure 4-3: Handwheel Interconnection to Aux I/O Connector




Figure 4-4: Handwheel Interconnection to the Aux I/O through a BBA32 Module

Chapter 5: Maintenance



IMPORTANT: For your own safety and for the safety of the equipment:

- Do not remove the cover of the XL5e.
- Do not attempt to access the internal components.

A fuse that needs to be replaced indicates that there is a more serious problem with the system or setup. Contact Global Technical Support for assistance.



DANGER: If you must remove the covers and access any internal components be aware of the risk of electric shock.

1. Disconnect the Mains power connection.
2. Wait at least ten (10) minutes after removing the power supply before doing maintenance or an inspection. Otherwise, there is the danger of electric shock.
3. All tests must be done by an approved service technician. Voltages inside the controller and at the input and output power connections can kill you.

Table 5-1: LED Description

LED	Color	Description
PWR	GREEN	The light will illuminate and remain illuminated while power is applied.
EN/FLT	GREEN	The axis is Enabled.
	RED	The axis is in a Fault Condition.
	GREEN/RED (alternates)	The axis is Enabled in a Fault Condition. or The light is configured to blink for setup.

Table 5-2: Troubleshooting

Symptom	Possible Cause and Solution
No Communication	Make sure the power LED is illuminated (this indicates that power is present).
	Make sure that all communication cables (HyperWire, for example) are fully inserted in their ports.

5.1. Preventative Maintenance

Do an inspection of the XL5e and the external wiring one time each month. It might be necessary to do more frequent inspections based on:

- The operating conditions of the system.
- How you use the system.

Table 5-3: Preventative Maintenance

Check	Action to be Taken
Examine the chassis for hardware and parts that are damaged or loose. It is not necessary to do an internal inspection unless you think internal damage occurred.	Repair all damaged parts.
Do an inspection of the cooling vents.	Remove all material that collected in the vents.
Examine the work area to make sure there are no fluids and no electrically conductive materials.	Do not let fluids and electrically conductive material go into the drive.
Examine all cables and connections to make sure they are correct.	Make sure that all connections are correctly attached and not loose. Replace cables that are worn. Replace all broken connectors.

Cleaning



DANGER: Before you clean the XL5e, disconnect the electrical power from the drive.

Use a clean, dry, soft cloth to clean the chassis of the drive. If necessary, you can use a cloth that is moist with water or isopropyl alcohol. If you use a moist cloth, make sure that moisture does not go into the drive. Also make sure that it does not go onto the outer connectors and components.

Do not use fluids and sprays to clean the drive because they can easily go into the chassis or onto the outer connectors and components. If a cleaning solution goes into the drive, internal contamination can cause corrosion and electrical short circuits.

Do not clean the labels with a cleaning solution because it might remove the label information.

5.2. Fuse Specifications



WARNING: Replace fuses only with the same type and value.

Table 5-4: Fuse Specifications

Fuse	Description	Size	Aerotech P/N	Third Party P/N
F100	Control Supply at Line Input (L)	2 A S.B.	EIF01044	Littelfuse 0877002.MXEP
F4	Motor Supply at AC1 (200 VAC/240 VAC)	7 A S.B.	EIF00107	Littelfuse 313007.HXP
F5	Motor Supply at AC1 (100 VAC/120 VAC)	8 A S.B.	EIF01022	Littelfuse 0215008.HXP
F6	XL5e-10: Motor Bus Voltage Negative	5 A S.B.	EIR01023	Littelfuse 0215005.HXP
	XL5e-20: Motor Bus Voltage Negative	10 A S.B.	EIR01020	Littelfuse 0215010.HXP
F7	XL5e-10: Motor Bus Voltage Positive	5 A S.B.	EIR01023	Littelfuse 0215005.HXP
	XL5e-20: Motor Bus Voltage Positive	10 A S.B.	EIR01020	Littelfuse 0215010.HXP

NOTE: F100 is located on the control board. F4, F5, F6, and F7 are located on the power supply board.

This page intentionally left blank.

Appendix A: Warranty and Field Service

Aerotech, Inc. warrants its products to be free from harmful defects caused by faulty materials or poor workmanship for a minimum period of one year from date of shipment from Aerotech. Aerotech's liability is limited to replacing, repairing or issuing credit, at its option, for any products that are returned by the original purchaser during the warranty period. Aerotech makes no warranty that its products are fit for the use or purpose to which they may be put by the buyer, whether or not such use or purpose has been disclosed to Aerotech in specifications or drawings previously or subsequently provided, or whether or not Aerotech's products are specifically designed and/or manufactured for buyer's use or purpose. Aerotech's liability on any claim for loss or damage arising out of the sale, resale, or use of any of its products shall in no event exceed the selling price of the unit.

THE EXPRESS WARRANTY SET FORTH HEREIN IS IN LIEU OF AND EXCLUDES ALL OTHER WARRANTIES, EXPRESSED OR IMPLIED, BY OPERATION OF LAW OR OTHERWISE. IN NO EVENT SHALL AEROTECH BE LIABLE FOR CONSEQUENTIAL OR SPECIAL DAMAGES.

Return Products Procedure

Claims for shipment damage (evident or concealed) must be filed with the carrier by the buyer. Aerotech must be notified within thirty (30) days of shipment of incorrect material. No product may be returned, whether in warranty or out of warranty, without first obtaining approval from Aerotech. No credit will be given nor repairs made for products returned without such approval. A "Return Materials Authorization (RMA)" number must accompany any returned product(s). The RMA number may be obtained by calling an Aerotech service center or by submitting the appropriate request available on our website (www.aerotech.com). Products must be returned, prepaid, to an Aerotech service center (no C.O.D. or Collect Freight accepted). The status of any product returned later than thirty (30) days after the issuance of a return authorization number will be subject to review.

Visit [Global Technical Support Portal](#) for the location of your nearest Aerotech Service center.

Returned Product Warranty Determination

After Aerotech's examination, warranty or out-of-warranty status will be determined. If upon Aerotech's examination a warranted defect exists, then the product(s) will be repaired at no charge and shipped, prepaid, back to the buyer. If the buyer desires an expedited method of return, the product(s) will be shipped collect. Warranty repairs do not extend the original warranty period.

Fixed Fee Repairs - Products having fixed-fee pricing will require a valid purchase order or credit card particulars before any service work can begin.

All Other Repairs - After Aerotech's evaluation, the buyer shall be notified of the repair cost. At such time the buyer must issue a valid purchase order to cover the cost of the repair and freight, or authorize the product(s) to be shipped back as is, at the buyer's expense. Failure to obtain a purchase order number or approval within thirty (30) days of notification will result in the product(s) being returned as is, at the buyer's expense.

Repair work is warranted for ninety (90) days from date of shipment. Replacement components are warranted for one year from date of shipment.

Rush Service

At times, the buyer may desire to expedite a repair. Regardless of warranty or out-of-warranty status, the buyer must issue a valid purchase order to cover the added rush service cost. Rush service is subject to Aerotech's approval.

On-site Warranty Repair

If an Aerotech product cannot be made functional by telephone assistance or by sending and having the customer install replacement parts, and cannot be returned to the Aerotech service center for repair, and if Aerotech determines the problem could be warranty-related, then the following policy applies:

Aerotech will provide an on-site Field Service Representative in a reasonable amount of time, provided that the customer issues a valid purchase order to Aerotech covering all transportation and subsistence costs. For warranty field repairs, the customer will not be charged for the cost of labor and material. If service is rendered at times other than normal work periods, then special rates apply.

If during the on-site repair it is determined the problem is not warranty related, then the terms and conditions stated in the following "On-Site Non-Warranty Repair" section apply.

On-site Non-Warranty Repair

If any Aerotech product cannot be made functional by telephone assistance or purchased replacement parts, and cannot be returned to the Aerotech service center for repair, then the following field service policy applies:

Aerotech will provide an on-site Field Service Representative in a reasonable amount of time, provided that the customer issues a valid purchase order to Aerotech covering all transportation and subsistence costs and the prevailing labor cost, including travel time, necessary to complete the repair.

Service Locations

<http://www.aerotech.com/contact-sales.aspx?mapState=showMap>

USA, CANADA, MEXICO

Aerotech, Inc.
Global Headquarters

CHINA

Aerotech China
Full-Service Subsidiary

GERMANY

Aerotech Germany
Full-Service Subsidiary

TAIWAN

Aerotech Taiwan
Full-Service Subsidiary

UNITED KINGDOM

Aerotech United Kingdom
Full-Service Subsidiary

Appendix B: Voltage Selection Operation



DANGER: Voltage selector settings must not be changed with Mains power applied to the unit.



DANGER: Wait at least ten (10) minutes after removing the power supply before performing maintenance or an inspection. Otherwise, there is the danger of electric shock.



WARNING: The voltage selector must be configured to match the AC line voltage on the Motor Supply Connector and is factory-configured based on the options that you ordered. You could damage the unit if the voltage selector is set for the incorrect AC input voltage.

The voltage selector can only be used with transformer-derived bus voltages. This voltage selector function should not be changed when using off-line supplies. Damage to the unit may result if this function is used improperly.

If the user changes the voltage selector settings, it is also the user's responsibility to change the XL5e AC power label located next to the Motor Supply connector. Refer to the [Section 1.1](#) for power ratings.

Procedure for setting AC voltage selector switches:

1. Turn-off and disconnect all power from unit.
2. Set the S1 and S2 switches for your voltage on the Motor Supply Connector.
NOTE: Refer to [Figure B-1](#) to see how switch position relates to voltage selection.
3. Apply a visible indicator on the drive that lets the user know that the voltage input configuration has changed and that the factory order part number no longer represents the current configuration.




Figure B-1: Voltage Selection Switch Access

Appendix C: Revision History

Revision	Description
1.02	The following sections have been updated: <ul style="list-style-type: none">• EU Declaration of Conformity• Agency Approvals
1.01	<ul style="list-style-type: none">• Control Supply specifications have been updated• Dimension drawings have been updated• Absolute Encoder support on the Auxiliary I/O connector has been added.• System Wiring (best practices) drawing has been added• Appendix B has been updated
1.00	New manual

This page intentionally left blank.

Index

-			
-EB1			
Analog Inputs	88		
Analog Outputs	87		
Digital Inputs	84		
Digital Outputs	80		
I/O Option Board	79		
Position Synchronized Output (PSO) Interface	89		
-MX2	40		
-MX3	40,60		
2			
2006/42/EC	9		
2011/65/EU	9		
2014/30/EU	9		
2014/35/EU	9		
A			
Absolute Encoder (Auxiliary I/O Connector)	59		
Absolute Encoder (Feedback Connector)	39		
Absolute Encoder Schematic (Auxiliary I/O Connector)	59		
Absolute Encoder Schematic (Feedback Connector)	39		
Altitude	23		
Ambient Temperature	23		
Analog Encoder (Auxiliary I/O Connector)	60		
Analog Encoder (Feedback Connector)	40		
Analog Encoder Phasing Reference Diagram	40,60		
Analog Encoder Schematic (Auxiliary I/O Connector)	61		
Analog Encoder Schematic (Feedback Connector)	41		
Analog Encoder Specifications (Auxiliary I/O Connector)	60		
Analog Encoder Specifications (Feedback Connector)	40		
Analog Input 0 on the Aux I/O Connector	71		
Analog Input 0 Schematic (Aux I/O Connector)	71		
Analog Input 0 Specifications (Aux I/O Connector)	71		
Analog Input Connector [-EB1] Mating Connector Part Numbers	88		
Analog Input Connector Pinout [-EB1]	88		
Analog Input Pins (Aux I/O Connector)	71		
Analog Input Typical Connection [-EB1]	88		
Analog Inputs [-EB1]	88		
Analog Output 0 on the Aux I/O Connector	70		
Analog Output 0 Schematic (Aux I/O Connector)	70		
Analog Output 0 Specifications (Aux I/O Connector)	70		
Analog Output Connector [-EB1] Mating Connector Part Numbers	87		
Analog Output Connector Pinout [-EB1]	87		
Analog Output Pins (Aux I/O Connector)	70		
Analog Output Specifications [-EB1]	87		
Analog Output Typical Connection [-EB1]	87		
Analog Outputs [-EB1]	87		
Aux I/O Connector			
Analog Input 0	71		
Analog Output 0	70		
Auxiliary Encoder Inputs	57		
Digital Outputs	64		
High-Speed User Inputs	69		
Position Synchronized Output	62		
PSO	62		
Aux I/O Connector Mating Connector Part Numbers	56		
Auxiliary Encoder Inputs (Aux I/O Connector)	57		
Auxiliary I/O Connector	56		
Analog Encoder	60		
Sine Wave Encoder	60		
Auxiliary I/O Connector Pinout	56		
Auxiliary I/O Pins (Aux I/O Connector)	57		
B			
BiSS absolute encoder	39,59		
Brake Connected to the Feedback Connector	49		
Brake Control Relay Specifications	49		
Brake Output Connector Pinout	72		
Brake Output Pins on the Feedback Connector	49		
Brake Outputs (Feedback Connector)	49		
Brake Power Supply Connector	72		
Brake Power Supply Connector Mating Connector Part Numbers	72		
Brushless Motor Configuration (Motor Power Output Connector)	29		
Brushless Motor Connections (Motor Power Output Connector)	29		
Brushless Motor Phasing Goal	31		
Brushless Motor Phasing Oscilloscope Example	31		
Brushless Motor Powered Motor Phasing	30		
Brushless Motor Unpowered Motor and Feedback Phasing	31		

C			
Cable Wires		EB1]	
Brushless Motors	29	Digital Inputs Connected to a Current Sourcing Device [-EB1]	86
DC Brush Motors	32	Digital Inputs Connected to Current Sinking Devices (Aux I/O Connector)	68
Stepper Motors	34	Digital Inputs Connected to Current Sourcing Devices (Aux I/O Connector)	68
Cables		Digital Inputs Schematic (Aux I/O Connector)	67
HyperWire	73	Digital Inputs Schematic [-EB1]	85
Sync Port	74	Digital Output 1 Connector [-EB1] Mating Connector Part Numbers	81
Cables and Accessories	91	Digital Output 1 Connector Pinout [-EB1]	81
cables, examining	96	Digital Output 2 Connector [-EB1] Mating Connector Part Numbers	81
Check for fluids or electrically conductive material exposure	96	Digital Output 2 Connector Pinout [-EB1]	81
Cleaning	96	Digital Output Pins (Aux I/O Connector)	64
Commands		Digital Output Schematic (Aux I/O Connector)	65
Sync	74	Digital Output Specifications (Aux I/O Connector)	64
Conducted and Radiated Emissions	9	Digital Output Specifications [-EB1]	80
connections, examining	96	Digital Outputs (Aux I/O Connector)	64
Control Board Fuse Specifications	97	Digital Outputs [-EB1]	80
Control Supply Connections	26	Digital Outputs Connected in Current Sinking Mode (Aux I/O Connector)	66
Control Supply Connector	26	Digital Outputs Connected in Current Sinking Mode [-EB1]	83
Mating Connector Part Numbers	26	Digital Outputs Connected in Current Sourcing Mode (Aux I/O Connector)	66
Wiring Specifications	26	Digital Outputs Connected in Current Sourcing Mode [-EB1]	83
cooling vents, inspecting	96	Digital Outputs Schematic [-EB1]	82
Customer order number	25	Dimensions	21
		Dimensions (without -EB1)	21
		Dimensions with -EB1	22
		Drawing number	25
		Drive and Software Compatibility	24
		E	
		Electrical Safety for Power Drive Systems	9
		Electrical Specifications	19
		Electromagnetic Compatibility (EMC)	9
		Enclosure	20
		encoder	
		absolute	39,59
		Encoder and Hall Signal Diagnostics	30
		Encoder Fault Input (Feedback Connector)	45
		Encoder Fault Input Pin on the Feedback Connector	45
		Encoder Input (Feedback Connector)	37

Encoder Input Pins on the Feedback Connector	37	Absolute Encoder Schematic (Auxiliary I/O Connector)	59
Encoder Phasing	42	Absolute Encoder Schematic (Feedback Connector)	39
Encoder Phasing Reference Diagram	42	Analog Encoder Schematic (Auxiliary I/O Connector)	61
End of Travel Limit Input (Feedback Connector)	46	Analog Encoder Schematic (Feedback Connector)	41
End of Travel Limit Input Connections	47	Analog Input 0 Schematic (Aux I/O Connector)	71
End of Travel Limit Input Diagnostic Display	48	Analog Input Typical Connection [-EB1]	88
End of Travel Limit Input Pins on the Feedback Connector	46	Analog Output 0 Schematic (Aux I/O Connector)	70
End of Travel Limit Input Schematic	47	Analog Output Typical Connection [-EB1]	87
End of Travel Limit Phasing	48	Brake Connected to the Feedback Connector	49
EnDat absolute encoder	39,59	Brushless Motor Configuration (Motor Power Output Connector)	29
Environmental Specifications	23	Control Supply Connections	26
EU 2015/863	9	DC Brush Motor Configuration (Motor Power Output Connector)	32
examining parts		Digital Inputs Connected to a Current Sinking Device [-EB1]	86
cables	96	Digital Inputs Connected to a Current Sourcing Device [-EB1]	86
connections	96	Digital Inputs Connected to Current Sinking Devices (Aux I/O Connector)	68
examining, dangerous fluids	96	Digital Inputs Connected to Current Sourcing Devices (Aux I/O Connector)	68
examining, dangerous material	96	Digital Inputs Schematic (Aux I/O Connector)	67
		Digital Inputs Schematic [-EB1]	85
F		Digital Output Schematic (Aux I/O Connector)	65
F100	97	Digital Outputs Connected in Current Sinking Mode (Aux I/O Connector)	66
F4	97	Digital Outputs Connected in Current Sourcing Mode (Aux I/O Connector)	66
F5	97	Digital Outputs Schematic [-EB1]	82
F6	97	Dimensions (without -EB1)	21
F7	97	Dimensions with -EB1	22
Feature Summary	16	End of Travel Limit Input Connections	47
Feedback Connector	36	End of Travel Limit Input Diagnostic Display	48
Absolute Encoder	39,59	End of Travel Limit Input Schematic	47
Analog Encoder	40	Hall-Effect Inputs Schematic	43
Brake Outputs	49	High-Speed Inputs	69
Encoder Fault Input	45	Home Limit Input Connections	47
Encoder Input	37	Home Limit Input Diagnostic Display	48
End of Travel Limit Input	46	Home Limit Input Schematic	47
Hall-Effect Inputs	43	Isolated Output Current Sinks Schematic (PSO)	90
Home Limit Input	46	Isolated Output Current Sources Schematic (PSO)	90
Pinout	36	Motor Supply Connections	27
Primary Encoder Input	37	Outputs Connected in Current Sinking Mode [-IO]	83
RS-422 Line Driver Encoder	38,58	Outputs Connected in Current Sourcing Mode [-EB1]	83
Sine Wave Encoder	40	Positive Motor Direction	30
Square Wave Encoder	38,58		
Thermistor Input	44		
Travel Limit Input	46		
Feedback Monitoring	30		
Figure			
-EB1 I/O Option Board Connectors	79		

PSO Interface (Aux I/O Connector)	63	I	
PSO Isolated Output Sinks Current	90	I/O Option Board [-EB1]	79
PSO Isolated Output Sources Current	90	Input Power Connections	26
PSO TTL Outputs Schematic	90	inspecting cooling vents	96
Sine Wave Encoder Schematic (Auxiliary I/O Connector)	61	Inspection	96
Sine Wave Encoder Schematic (Feedback Connector)	41	Installation and Configuration	25
Square Wave Encoder Inputs Schematic (Aux I/O Connector)	58	Installation Connection Overview	13
Square Wave Encoder Schematic (Feedback Connector)	38	Installation Overview	13
Stepper Motor Configuration	34	Introduction	15
STO Timing	55	IP54 Compliant	20
Thermistor Input Schematic	44	Isolated Output Current Sinks Schematic (PSO)	90
TTL Outputs Schematic (PSO)	90	Isolated Output Current Sources Schematic (PSO)	90
Typical STO Configuration	51		
fluids, dangerous	96	J	
Functional Diagram	18	Joystick Interface	92
Fuse Specifications	97		
Control Supply at L	97	L	
External Shunt (-SX1)	97	Laser Firing	62
Motor Supply at AC1	97		
		M	
H		Maintenance	95
Hall-Effect Feedback Pins on the Feedback Connector	43	material, electrically conductive	96
Hall-Effect Inputs (Feedback Connector)	43	Mating Connector	
Hall-Effect Inputs Schematic	43	Analog Output Connector [-EB1]	87
Handwheel Interconnection (to Aux I/O through a BBA32 Module)	94	Mating Connector P/N	
Handwheel Interconnection to the Aux I/O Connector	94	Analog Input Connector [-EB1]	88
Handwheel Interface	94	Aux I/O Connector	56
High-Speed Input Pins on the Aux I/O Connector	69	Brake Power Supply Connector	72
High-Speed Input Specifications	69	Control Supply Connector	26
High-Speed Inputs	69	Digital Input 1 Connector [-EB1]	84
High-Speed User Inputs (Aux I/O Connector)	69	Digital Input 2 Connector [-EB1]	85
Home Limit Input (Feedback Connector)	46	Digital Output 1 Connector [-EB1]	81
Home Limit Input Connections	47	Digital Output 2 Connector [-EB1]	81
Home Limit Input Diagnostic Display	48	Feedback Connector	36
Home Limit Input Pins on the Feedback Connector	46	Motor Power Output Connector	28
Home Limit Input Schematic	47	Motor Supply Connector	27
Humidity	23	PSO Connector [-EB1]	89
HyperWire	73	STO Connector	50
Cable Part Numbers	73	Mechanical Specifications	20
Card Part Number	73	Motor Connector	
		Mating Connector Part Numbers	36
		Motor Function Relative to STO Input State	54

Sine Wave Encoder Phasing Reference Diagram	40,60	Electrical Specifications	51
Sine Wave Encoder Schematic (Auxiliary I/O Connector)	61	External Delay Timer	53
Sine Wave Encoder Schematic (Feedback Connector)	41	Functional Description	53
Sine Wave Encoder Specifications (Auxiliary I/O Connector)	60	Mating Connector Part Numbers	50
Sine Wave Encoder Specifications (Feedback Connector)	40	Motor Function Relative to the STO Input State	54
Specifications		Signal Delay	54
Analog Encoder (Auxiliary I/O Connector)	60	Standards	52
Analog Encoder (Feedback Connector)	40	Standards Data	52
Analog Input 0 (Aux I/O Connector)	71	Startup Validation Testing	54
Analog Output 0 (Aux I/O Connector)	70	Timing	55
Analog Outputs [-EB1]	87	Typical Configuration	51
Brake Control Relay	49	Sync-Related Commands	74
Control Board Fuses	97	Sync Port Cables	74
Control Supply Connector Wiring	26	Sync Ports	74
Differential Analog Inputs [-EB1]	88	System part number	25
Digital Inputs (Aux I/O Connector)	67		
Digital Inputs [-EB1]	84	T	
Digital Outputs (Aux I/O Connector)	64	Table of Contents	3
Digital Outputs [-EB1]	80	Thermistor Input (Feedback Connector)	44
High-Speed Inputs	69	Thermistor Input Pin on the Feedback Connector	44
Motor Supply Connector Wiring	27	Thermistor Input Schematic	44
Power Supply Board Fuses	97	Travel Limit Input (Feedback Connector)	46
PSO (Aux I/O Connector)	62	TTL Outputs Schematic (PSO)	90
PSO [-EB1]	89	Two Axis Joystick Interface	92
RS-422 Encoder (Feedback Connector)	38,58	Two Axis Joystick Interface (to the I/O board of two drives)	93
Sine Wave Encoder (Auxiliary I/O Connector)	60	Typical STO Configuration	51
Sine Wave Encoder (Feedback Connector)	40		
Square Wave Encoder (Feedback Connector)	38,58	U	
STO Electrical Specifications	51	Unit Weight	20
Unit Weight	20	Unpacking the Chassis	25
Square Wave Encoder	38,58	Use	23
Square Wave Encoder Inputs Schematic (Aux I/O Connector)	58		
Square Wave Encoder Schematic (Feedback Connector)	38	V	
Square Wave Encoder Specifications (Feedback Connector)	38,58	Voltage Selection	101
Standard Features	16	Voltage Selection Switch	102
Stepper Motor Configuration	34		
Stepper Motor Connections (Motor Power Output Connector)	34	W	
Stepper Motor Phasing	35	Warranty and Field Service	99
STO	50	Wire Colors for Aerotech-Supplied Brushless Motor Cables	29
Connector Pinout	50	Wire Colors for Aerotech-Supplied DC Brush Motor Cables	32
Diagnostics	55	Wire Colors for Aerotech-Supplied Stepper Motor Cables	34